West Bengal State Electricity Distribution Company Limited

RATE CONTRACT ALL IN ONE

CONTENTS

SL.	PARTICULARS	PAGE NOS	OFFICE ORDER REF
1	RATES FOR NEW CONSTRUCTION WORK	1-3	CED/13 DT. 15.05.2018
2	RATES FOR NEW SPECIAL O&M WORK	4-9	CED/14 DT. 15.05.2018
3	NEW ERECTION RATES FOR L.T. & H.T. AB CABLE	10-11	CED/15 DT. 15.05.2018
4	ERECTION, LAYING, MAINTENANCE OF 11KV U.G. ELECTRICAL NETWORK SYSTEM.	12-19	CED/UG Cable Rate Contract/ 07 DT. 25.02.2020
5	ERECTION, LAYING, MAINTENANCE OF 33KV U.G. ELECTRICAL NETWORK SYSTEM.	20-22	CED/44 DT. 17.11.2018
5	COST DATA OF MATERIALS (2021-2022) BOTH CENTRALISED AND LOCAL ITEMS FOR 33KV, 11KV & LT SYSTEMS.	23-34	CED/L-14A/198 DT. 18.06.2021
6	RATE CONTRACT FOR REPAIRING OF DAMAGE/ DEFECTIVE DISTRIBUTION TRANSFORMER.	35-40	P&C/P-35/2017-18/DTR/RC/PC-III/78 DT. 24.06.19 & 80-195 DT. 25.06.19

ERECTION RATE FOR NEW CONSTRUCTION WORKS-2018

SL. NO.	DESCRIPTION OF ITEM				UNIT	RATE (in Rs.)	
						WITH PAINTING	WITHOUT PAINTING
1	SURVEY (PRELIM. & FINAL) FOR HVOH LINE UPTO 33 KV	i)	SURVEY (PRELIM. & FINAL) FOR HVOH LINE UPTO 33 KV		KM		2761.00
2	DO FOR L&MV OH LINE	ii)	DO FOR L&MV OH LINE		KM		1714.00
3	ERECTION OF SINGLE POLE WITH FOUNDATION BUT WITHOUT ANY FITTINGS	i)	RAIL POLE UPTO 12.8 METRE		NO	4351.00	3835.00
		ii)	SOLID PCC POLE 9 MTR. LONG		NO		2281.00
		iii)	SOLID PCC POLE 8 MTR. LONG		NO		1501.00
		iv)	STEEL TUBULER POLE 9 MTR. LONG		NO	2575.92	2333.00
		v)	STEEL TUBULER POLE 11 MTR. LONG		NO	3127.30	2860.00
4	ERECTION OF SINGLE POLE COMPLETE WITH ALL FITTINGS i.e, V- BRACKET, TOP ADAPTOR ETC. AND FOUNDATION BUT WITHOUT ANY INSULATOR FOR HV OH LINE UPTO 33 KV	i)	RAIL POLE UPTO 12.8 MTR. LONG		NO	4657.00	4141.00
		ii)	SOLID PCC POLE 9 MIR. LONG		NO	2620.00	2534.00
		iii)	SOLID PPC POLE 8 MTR. LONG		NO	1766.00	1680.00
		iv)	STEEL TUBULER POLE 9 MTR. LONG		NO	2774.92	2445.00
		v)	DO BUT 11 MTR. LONG		NO	3596.30	3221.00
5	ERECTION OF DOUBLE POLE STRUCTURE COMPLETE WITH ALL FITTINGS AND FOUNDATION BUT WITHOUT ANY INSULATOR FOR HV OH LINE UPTO 33 KV	i)	RAIL POLE UPTO 12.81 MTR. LONG		NO	13969.00	12421.00
		ii)	SOLID PCC POLE 9 MTR. LONG		NO	9438.00	8922.00
		iii)	SOLID PCC POLE 8 MTR. LONG		NO	6170.00	5654.00
		iv)	STEEL TUBULAR POLE 9 MIR.		NO	7285.84	6211.00
		v)	STEEL TUBULAR POLE 11 MTR.		NO	7455.60	6238.00
6	ERECTION OF TRIPPLE POLE STRUCTURE COMPLETE WITH ALL FITTINGS AND FOUNDATIONS BUT WITHOUT INSULATOR FOR HV OH LINE UPTO 33 KV	i)	RAIL POLE UPTO 12.81 MIR. LONG		NO	23364.00	20784.00
		ii)	PCC POLE SOLID 9 MTR. LONG		NO	16274.00	15242.00
		iii)	PCC POLE SOLID 8 MTR. LONG		NO	12044.00	11012.00
		iv)	STEEL TUBULAR POLE 9 MTR.		NO	19341.76	17350.00
		v)	STEEL TUBULAR POLE 11 MTR.		NO	19595.90	17390.00
7	ERECTION Of FOUR POLE STRUCTURE COMPLETE WITH ALL FITTINGS AND FOUNNDATIONS BUT WITHOUT ANY INSULATOR FOR HV OH LINE UPTO 33 KV	i)	RAILPOLE UPTO 12.81 MTR. LONG		NO	35717.00	31675.00
		ii)	PCC POLE SOLID 9 MTR. LONG		NO	27829.68	24572.00
		iii)	PCC POLE SOLID 8 MTR. LONG		NO	15312.00	13334.00
		iv)	STEEL TUBULAR POLE 9 TO 11 MTR.		NO	30314.00	26960.00
8	EXTENSION OF SINGLE POLE COMPLETE WITH ALL FITTINGS UPTO 3 MTR. LENGTH BUT WITHOUT INSULATOR FOR HV OH LINE UPTO 33 KV	i)	RAIL POLE		NO	1862.95	1663.00
		ii)	SOLID PCC POLE 8 MTR. LONG		NO	1706.38	1506.00
9	ERECTION OF SUB-STATION STRUCTURE COMPLETE WITH ALL FITTINGS ie. FITTINGS FOR ISOLATOR. FUSE UNIT, TRANSFORMER, KIOSK, MS HOOD, TOP CHANNELON ETC. AND FOUNDATION BUT WITHOUT INSULATOR.	i)	RAIL POLE SUPPORT (D.P.)		NO	16112.00	15252.00
		ii)	PCC POLE SOLID 9 MTR. LONG (D.P.)		NO	13169.00	12309.00
		iii)	PCC POLE SOLID 8 MTR. LONG (D.P.)		NO	10735.00	9875.00
		iv)	4 POLE STRUCTURE OF 8 MTR. LONG PCC POLE		NO	19872.00	19012.00
10	ERECTION OF CONDUCTOR INCLUDING LAYING, HOISTING, STRINGING, JOINTING, SAGGING, TENSIONING & ROUTE CLEARANCE	i)	a) 150 Sq. mm. ACSR 'WOLF' OR EQI. SIZE OF AAAC	3 WIRE	KM		19208.00
		ii)		2 WIRE	KM		14154.00
		iii)		1 WIRE	KM		9246.00
		i)	a) 100 Sq. mm. ACSR 'DOG' OR EQI. SIZE OF AAAC	3 WIRE	KM		16544.00
		ii)		2 WIRE	KM		12330.00
		iii)		1 WIRE	KM		8169.00
		i)	b) 50 Sq. mm. ACSR 'RABIT' OR EQI. SIZE OF AAAC	4 WIRE	KM		9715.00
		ii)		3 WIRE	KM		8289.00
		iii)		2 WIRE	KM		6184.00
		iv)		1 WIRE	KM		2978.00

Prepared by: Dhrubabrata Roy

ERECTION RATE FOR NEW CONSTRUCTION WORKS-2018

SL. NO.	DESCRIPTION OF ITEM				UNIT	RATE (in Rs.)	
						WITH PAINTING	WITHOUT PAINTING
	ERECTION OF CONDUCTOR INCLUDING LAYING, HOISTING, STRINGING, JOINTING, SAGGING, TENSIONING & ROUTE CLEARANCE	i)	c) 30Sq. mm. ACSR 'WEASEL' OR EQl. SIZE OF AAAC	4 WIRE	KM		8821.00
		ii)		3 WIRE	KM		7899.00
		iii)		2 WIRE	KM		5322.00
		iv)		1 WIRE	KM		2845.00
		iI	d) 20 Sq. mm. ACSR 'SQIRREL' OR EQl. SIZE OF AAAC	4 WIRE	KM		8432.00
		ii)		3 WIRE	KM		7043.00
		iii)		2 WIRE	KM		4873.00
		iv)		1 WIRE	KM		2894.00
11	ERECTION OF CONDUCTOR INCLUDING LAYING, HOISTING, STRINGING, JOINTING, SAGGING, TENSIONING & ROUTE CLEARANCE	i)	e) 50 Sq. mm. AAC 'ANT'	4 WIRE	KM		7972.00
		ii)		3 WIRE	KM		6882.00
		iii)		2 WIRE	KM		4864.00
		iv)		1 WIRE	KM		2815.00
		i)	f) 25 Sq. mm. AAC 'GNAT'	4 WIRE	KM		7136.00
		ii)		3 WIRE	KM		6301.00
		iii)		2 WIRE	KM		4412.00
		iv)		1 WIRE	KM		2435.00
		g)	g) 4-5 mm G.I Wire	1 WIRE	KM		1592.00
11	ERECTION OF DISTRIBUTION TRANSFORMER COMPLETE WITH ALL FITTINGS (O/D TYPE)	i)	10/I6 KVA 11/0.43 KV		NO		1885.00
		ii)	25 KVA 11/0.43 KV		NO		1925.00
		iii)	63 KVA 11/0.43 KV		NO		2711.00
		iv)	100 KVA 11/0.43 KV		NO		3214.00
		v)	315 KVA 11/0.43 KV		NO		7248.00
12	A) FABRICATION & FIXING OF CRADLE GUARD BRACKET	i)	SINGLE POLE		NO		237.00
		ii)	DOUBLE POLE		NO		369.00
	B) LEAD WIRE (a) UPTO 30 MTRS.	i)	2 WIRE		NO		256.00
		ii)	4 WIRE		NO		357.00
	DO (b) ABOVE 30 MTR. BUT UPTO 60 MTR.	i)	2 WIRE		NO		312.00
		ii)	4 W IRE		NO		469.00
	DO (c) ABOVE 60 MTR. BUT UPTO 100 MTR.	i)	2 W IRE		NO		506.00
		ii)	4 WIRE		NO		746.00
	C) MAKING & FIXING OF CROSS LESSING WIRE	i)			NO		15.00
13	FIXING OF INSULATOR	i)	11 KV PIN INSULATOR WITH PIN		NO		63.00
		ii)	33 KV PIN INSULATOR WITH PIN		NO		72.00
		iii)	11 KV DISC INSULATOR WITH STRAIN HARDWARE		NO		65.00
		iv)	33 KV DISC (ie. 3 NOS. 11 KV DISC INSULATOR WITH STRAIN HARDWARE		NO		107.00
		v)	LT SHACKLE INSULATOR WITH 1 NO. G.I NUTS & BOLTS		NO		52.00
		vi)	LT SHACKLE INSULATOR (NUTS & BOLTS TO BE SUPPLIED BY BOARDS)		NO		37.00
		vii)	LT PIN WITH INSULATOR		NO		37.00
14	FIXING OF C.I. REEL WITH MS NUTS & BOLTS	i)			NO		46.00
15	STAY SET COMPLETE WITH ALL FITTINGS, GUY INSULATOR BINDING ETC.	i)	HT STAY SET (1830X20 mini		NO		641.00
		ii)	LT STAY SET (1630 X 10 mm)		NO		555.00
16	EARTHING COMPLETE WITH DRIVING OF EARTH SPIKE & CONNECTION OF EARTH ELECTRODE WITH NON CURRENT CARRIN METALIC PARTS OF SUPPORTS. STAY WIRE, CRADLE GUARDS, L.A. ETC.				NO		313.00
17	ANTI CLIMBING DEVICE WITH BARBED WIRES				NO		150.00

Prepared by: Dhrubabrata Roy

ERECTION RATE FOR NEW CONSTRUCTION WORKS-2018

SL. NO.	DESCRIPTION OF ITEM			UNIT	RATE (in Rs.)	
					WITH PAINTING	WITHOUT PAINTING
a	FINING OF CAUTION HOARD			NO		24.00
19	NUMBERING OP POLES			NO		21.00
20	FIXING OF SAFETY DEVICE ON L&MV O.H. LINE			NO		35.00
21	FIXING OF ANGLE IRON BRACKET ON SINGLE PCC POLE FOR L&MV LINE			NO	605.00	596.00
22	FIXING OF 11 KV T.P.G.O. ISOLATOR ON SUB-STATION STRUCTURE WITH PROPER ADJUSTMENT			NO		1193.00
23	FIXING OF 11 KV T.P.G.O. ISOLATOR ON-LINE STRUCTURE (D.P. OR ANY COMPOUND STRUCTURE) INCLUDING FIXING OF SUPPORTS eg. CHANNEL, CLAMP ETC. WITH PROPER ADJUSTMENT.			NO	3199.00	3165.00
24	FIXING OF 11 KV ISOLATING LINK UNIT ON STRUCTURE WITH PROPER ADJUSTMENT			NO		986.00
2S	FIXING OF 11 KV LIGHTNING ARRESTER ON STRUCTURE (1 SET OF 3 L.A.S)			NO		339.00
26	FIXING OF MS BOX BRACKETS ON POLE FOR L& MV LINE			NO	1433.00	1414.00
27	FIXING OF MAIN SWITCH AND MS HOOD AND COMPLETE CONNECTION WITH PVC CABLE	i)	SINGLE SWITCH	NO	1081.00	1057.00
		ii)	DOUBLE SWITCH	NO	1636.00	1606.00
28	FIXING OF KIOSK AND MAIN SWITCH AND COMPLETE CONNECTION WITH PVC CABLE	i)	SINGLE SWITCH	NO	2238.00	2155.00
		ii)	DOUBLE SWITCH	NO	3100.00	3012.00
29	FIXING OF SOLID TEE OFF BRACKET WITHOUT INSULATOR	i)	SINGLE POLE	NO	1510.00	1495.00
		ii)	DOUBLE POLE	NO	1498.00	1483.00
30	RAIL POLE CUTTING	i)		NO		394.00
31	MAKING HOLE ON RAIL POLE	i)		NO		110.00
32	FIXING OF LT SPACER WITH L & MVII.O.	i)	1-PHASE UNIT	NO		37.00
		ii)	3-PHASE UNIT	NO		56.00
33	FIXING OF MS HOOD ONLY	i)		NO	543.00	519.00
34	FITTING/FIXING OF DEAD END/TENSION CLAMP INCLUDING COMPRESSION JOINT WITH WOLF CONDUCTOR/PER COND	i)		NO		201.00
	FITTINGS/FIXING OF SUSPENSION CLAMP FOR WOLF CONDUCTOR/COND	ii)		NO		30.00
	FITTING/FIXING OF JUMPER FOR WOLF CONDUCTOR WITH COMPRESSION JOINT/COND	iii)		NO		148.00
	JOINTING OF WOLF CONDUCTOR BY COMPRESSION JOINT PER COND.	iv)		NO		244.00
35	PROVIDING MUFFING AT THE BASE OF STEEL TUBULAR POLE WITH CEMENT CONCRETE (1:3:6) INCLUDING SHUTTERING, THE MUFFING SHOULD BE 600 MM ABOVE G.L AND ISO MM BELOW G.L AND TOP SHOULD BE CHAMFERED			NO		774.00

NB - THE SCHEDULE INCUDES ERECTION OF EACH RAIL I'OLE WITH 450 VI DO MM THICK CEMENT CONCRETE (1:3:6) BASE BLOCK BELOW I'OLE AND HARD JHAM A METAL CEMENT CONCRETE (1:2:4) WITH 0.30 MTR. MUFFING ABOVE GROUND LEV EL INCLUDING NEAT CEMENTED FINISH.

ERECTION RATE FOR SPECIAL (O&M) WORK

SL NO	DESCRIPTION OF ITEM	RATE (in Rs.)
1	DISMANTLING OF DIST.TRANSFORMER FROM EXISTING STRUCTURE AND RETURNING THE SAME TO STORE	
a)	10/16 KVA, 11/0.4KV	918.00
b)	25 KVA,11/0.4 KV	918.00
c)	63 KVA, 11/0.4 KV	1203.00
d)	100 KVA,11/0.4 KV	1489.00
e)	250/315 KVA,11/0.4 KV	2978.00
2	DISMANTLING OF DIST.TRANSFORMER FROM EXISTING STRUCTURE AND RETURNING THE SAME TO STORE AND INSTALLATION OF A NEW TRANSFORMER OF SAME CAPACITY OF THE ABOVE STRUCTURE INCLUDING TRANSPORTATION FROM STORE	
i	10/16 KVA, 11/0.4KV	1846.00
ii	25 KVA,11/0.4 KV	2141.00
iii	63 KVA, 11/0.4 KV	2808.00
iv	100 KVA,11/0.4 KV	3141.00
V	250/315 KVA,11/0.4 KV	6546.00
3	DISMANTLING OF DIST.TRANSFORMER FROM STRUCTURE, RETURNING TO STORE AND INSTALLATION OF ONE NEW TRANSFORMER OF HIGHER CAPACITY INCLUDING TRANSPORTATION FROM STORE .	
a)	1O KVA TO BE REPLACED BY 25 KVA	2205.00
b)	25 KVA TO BE REPLACED BY 63 KVA	2665.00
c)	63 KVA TO BE REPLACED BY 100 KVA	2998.00
d)	100 KVA TO BE REPLACED BY 250/315 KVA	5087.00
4	STRAIGHTENING OF POLES	
a)	8M.LONG PCC	292.00
b)	9M LONG PCC	408.00
c)	STEEL TUBELAR 9/11/13M LONG	333.00
d)	RAIL UP TO - 12.81 M LONG	483.00
c)	WOOD	292.00
5	DISMANTLING OF FITTINGS FROM EXISTING POLE AND REFIXING THE SAME ON NEW POLE AT SAME SITE :	
a)	V BRACKET /TOP ADOPTER OR EQUIVALENT SUBTITUTE 11 KV SYSTEM	150.00
b)	-DO- FOR 33 KV SYSTEM	193.00
6	FIXING V BRACKET TOP ADOPTER OR THEIR EQUIVALENT SUPPORT ON EXISTING POLE	
a)	FOR 8M LONG PCC POLE (without painting)	107.00
b)	FOR 8M LONG PCC POLE (with painting)	159.00
c)	FOR RAIL POLE (with painting)	194.00
7	DISMANTLING OF INSULATOR FROM EXISTING POLE & REFIXING THE SAME ON A POLE AT SAME SITE	
i)	11KV PIN WITH INSULATOR	53.00
ii)	33KV PIN WITH INSULATOR	61.00
iii)	11 KV DISC INSULATOR WITH HARDWARE	53.00
iv)	33KV DISC INSULATOR WITH HARDWARE (3NOS. DISC INSULATOR PER SET)	72.00

ERECTION RATE FOR SPECIAL (O&M) WORK

SL NO	DESCRIPTION OF ITEM	RATE (in Rs.)
v)	L.T. SHACKLE INSULATOR	38.00
8	DISMANTLING OF C.I.REEL FROM EXISTING POLE & REFIXING THE SAME ON A POLE AT SAME SITE	38.00
9	EARTHING WITH ALREADY EXIXTING DRIVEN EARTH SPIKE BY ONLY CONNECTING THE EARTH ELECTRODE WITH NON CURRENT CARRYING METAL PARTS BY MEANS OF SUITABLE SIZE OF G.I. WIRE	41.00
10	ERECTION OF STAY SET BY FIXING STAY WIRE OF SUITABLE SIZE, GUY INSULATOR ETC. ON EXISTING GROUTED, DRIVEN STAY SET	122.00
11	RESAGGING OF EXISTING CRADLE GUARD	
a)	2-WIRE :	
i)	LEAD WIRE UPTO 30 MTR.	79.00
ii)	LEAD WIRE ABOVE 30 MTR & UPTO 60 MTR.	111.00
iii)	LEAD WIRE ABOVE 60 MTR. UPTO 100 MTR.	139.00
b)	4-WIRE :	
i)	LEAD WIRE UPTO 30 MTR.	119.00
ii)	LEAD WIRE ABOVE 30 MTR & UPTO 60 MTR.	167.00
iii)	LEAD WIRE ABOVE 30 MTR & UPTO 100 MTR.	208.00
12	RE FIXING OF CROSS LACING	8.93
13	RESAGGING OF EXISTING CONDUCTOR PER KM	
a)	FOR SINGLE CONDUCTOR	
i)	i) 100 SQ. MM. ACSR/AAAC	1876.00
ii)	ii) 50 SQ. MM. ACSR/AAAC	712.00
iii)	iii) 30 SQ. MM. ACSR/AAAC	688.00
iv)	iv)20SQ. MM. ACSR	688.00
v)	v) 50 SQ. MM. AAC	675.00
vi)	vi)25SQ. MM. AAC	625.00
b)	FOR 2 CONDUCTOR	1.8 times of respective rate for single conductor will be applicable
c)	FOR 3 CONDUCTOR	2.4 times of respective rate for single conductor will be applicable
d)	FOR 4 CONDUCTOR	3.0 times of respective rate for single conductor will be applicable
14	DISMANTLING OF CONDUCTOR FROM O.H. LINES. COILING OR WINDING IN DRUMS(DRUM SUPPIED BY WBSEDCL) AND RETURNING TO STORE	
a)	FOR SINGLE CONDUCTOR	
i)	100 SQ. MM. ACSR/AAAC	3001.00
ii)	50 SQ. MM. ACSR/AAAC	1139.00
iii)	30 SQ. MM. ACSR/AAAC	1101.00
iv)	20 SQ. MM. ACSR	1101.00
v)	50 SQ. MM. AAC	1080.00

ERECTION RATE FOR SPECIAL (O&M) WORK

SL NO	DESCRIPTION OF ITEM	RATE (in Rs.)
vi)	25 SQ. MM. AAC	1000.00
b)	FOR 2 CONDUCTOR	1.8 times of respective rate for single conductor will be applicable
o)	FOR 3 CONDUCTOR	2.4 times of respective rate for single conductor will be applicable
d)	FOR 4 CONDUCTOR	3.0 times of respective rate for single conductor will be applicable
15	DISMANTLING OF L&MV SERVICE LINES FROM EXISTING SUPPORT & REFIXING OF THE SAME ON THE SAME SUPPORT OR A NEW SUPPORT AT SAME LOCATION	
i)	DOMESTIC/COMMERCIAL SERVICE	150.00
ii)	INDUSTRIAL SERVICE	193.00
16	REPLACEMENT OF UNSERVICEABLE SERVICE LINE BY ERECTING NEW CABLE/CONDUCTOR	230.00
17	DISMANTLING OF DEFFECTIVE UNSERVICEABLE TPGO ISOLATOR (ROCKING TYPE) AND REFIXING THE SAME ON SAME SUPPORT/STRUCTURE WITH NECESSARY ADJUSTMENT	
a)	33KV ISOLATOR	1757.00
b)	11KV ISOLATOR	1717.00
18	DISMANTLING OF L&MV SERVICE LINES WITH METER FROM EXISTING SUPPORT & RETURN OF DISMANTLED MATERIALS TO CONCERNED STORES	
i)	SINGLE PHASE SERVICE	245.00
ii)	THREE PHASE SERVICE	306.00
19	DISMENTLING OF OLD UNSERVICEABLE TPGO ISOLATOR (ROCKING TYPE AND RETURNING TO STORE WITH REPLACEMENT BY A NEW SET	
a)	FOR 33 KV ISOLATOR	2328.00
b)	FOR 11KV ISOLATOR	1717.00
20	UPROOTING OF POLE FROM EXISTING SITE AND RETURNT THE SAME TO STORE IN GOOD ORDER AND CONDITION	
a)	RAIL POLE(UPTO 12.81 MTRS)	1000.00
b)	PCC POLE 9M .LONG	594.00
c)	PCC POLE 8M .LONG	383.00
d)	STEEL TUBULAR POLE (UPTO 13MTRS)	630.00
21	DISMANTLING & REFIXING OF LT. BRACKET IN EXISTING POLE/STRUCTURE	487.00
22	REPLACEMENGT OF OLD /DAMAGED L.T.PVC CABLEON SUB STN. STRUTURE WITH NEW CABLE OF SAME SIZE/HIGHER SIZE INCLUDING NECESSARY SOCKETING & CONNECTION	
a)	FOR SINGLE CKT	342.00
b)	FOR DOUBLE CKT	458.00
23	DISMANTLING OF DEFECTIVE BROKEN SINGLE POLE OF D.P./T.P/4-REPLACEMENT OF THE SAME BY AN NEW ONE TO MAKE GOOD OF THE STRUCTURE WITH EXISTING FITING ETC.	

ERECTION RATE FOR SPECIAL (O&M) WORK

SL NO	DESCRIPTION OF ITEM	RATE (in Rs.)
a)	FOR PCC POLE - 8MTR	
i)	D.P.	2935.00
ii)	4 - POLE	5074.00
b)	FOR PCC POLE -9MTR	
i)	D.P.	4491.00
ii)	4 - POLE	9535.00
24	DISMANTLING OF POLE (SINGLE) AND REERECTION OF THE SAME AT THE SAME /ADJACENT LOCATION	
a)	RAIL POLE (UPTO 12.81MTRS)	4794.00
b)	PCC POLE 9MTR LONG	2851.00
c)	PCC POLE 8MTR LONG	1876.00
d)	STEEL TUBULAR POLE (UPTO 9M /l 1M/13M)	2916.00
25	CONVERSION OF EXISTING SINGLE POLE /STRUCTURE FOR MAKING DIST SUB STATION STRUCTURE WITH NECESSARY FONDATION AND FITTINGS BUT WITHOUT ISOLATOR AND INSULATOR	
a)	SINGLE TO D.P	
i)	ON RAIL POLE	11455.00
ii)	ON PCC POLE- 8MTR	8969.00
iii)	ON PCC POLE-9MTR	10549.00
b)	DP TO 4 - POLE ON 8MTR LONG PCC POLE	9137.00
26	ERECTION OF 33KV TPGO ISOLATOR (ROCKING TYPE ON STRUCTURE (DP) OR ANY COMPOUND STRUCTURE INCLUDDING FIXING SUPPORT ie. CHANNEL, CLAMP ETC., WITH NECESSARY FABRICATION & PROPER ADJUSTMENT (VERTICAL CONFIGURATION)	1589.00
27	SERVICE CONNECTION (SINGLE PHASE)	
a)	WITHOUT FIXING OF METER	308.00
b)	WITH FIXING OF METER ON TW BOARD INCLUDING SUPPLY OF FIXING MATERIALS & MAKING NECESSARY CONNECTION EXCLUDING SUPPLY OF METER, TW BOARD AND EARTHING DEVICE	504.00
28	SERVICE CONNECTION (3- PHASE) WITH FIXING OF METER ON PILFER PROOF BOX INCLUDING SUPPLY OF FIXING MATERIALS & MAKING NECESSARY CONNECTION EXCLUDING SUPPLY OF METER, PILFER PROOF BOX AND EARTHING DEVICE	570.00
29	FIXING OF PORCELAIN CUT OUT (a set of 3 nos.) IN PLACE OF MAIN SWITCH ON S/STN. STRUCTURE WITH NECESSARY CABLE CONNECTION	
a)	FOR SINGLE CKT.	630.00
b)	FOR DOUBLE CKT.	1037.00
30	FIXING OF 3-PHASE ENERGY METER (STATIC/ELECTROMAGNETIC) WITH PILFER PROOF METER BOX WITH RELATED ASSOCIATED WORKS AS PER FOLLOWING SCHEDULE :	676.00
a)	FIXING OF 60 AMP CUTOUT 3NOS. WITH NECESSARY CONNECTIONS.	
b)	DRAWING AND FIXING OF L.T. PVC CABLE OF REQUISITE SIZE FROM SERVICE POLE TO METER BOX WITH SUPPLY AND FIXING CABLE GLAND MADE OF BRASS AND OF REQUISITE SIZE AND NECESSARY OF CONNECTIONS WITH ALUMINIUM SOCKETING (SOCKETS TO BE SUPPLIED BY THE CONTRACTOR	

ERECTION RATE FOR SPECIAL (O&M) WORK

SL NO	DESCRIPTION OF ITEM	RATE (in Rs.)
c)	NECESSARY EARTH CONNECTIONS WITH METER AND METERING INSTALLATIONS.	
31	DISMANTLING OF EXISTING 3-PHASE ENERGY METER AND FIXING OF A NEW ONE WITH PILFER PROOF METER BOX AS PER THE FOLLOWING SCHEDULE.	884.00
a)	DISMANTLING OF EXISTING OF 3-PHASE ENERTY METER (STATIC/ELECTROMAGNITIC WITH ASSOCIATED INSTALLATION INCLUDING DEINSTALLING OF BARE SERVICE LINE (3-PHASE)AND RETURNING THE SAME TO STORE.	
b)	FIXING OF 3-PHASE ENERGY METER (STATIC/ELECTROMAGNETIC WITH PILFER PROOF METER BOX (TO BE SUPPLIED BY THE BOARD) WITH RELATED ASSOCIATED WORKS	
c)	FIXING OF 60 AMP CUT-OUT 3 NOS. WITH NECESSARY CONNECTIONS.	
	d) DRAWING AND FIXING OF L.T. PVC CABLE OF REQUISITE SIZE FROM SERVICE POLE TO METER BOX WITH SUPPLY AND FIXING CABLE GLOAND MADE OF BRASS AND OF REQUISITE SIZE AND NECESSARY CONNECTION WITH ALUMINIUM SOCKETING(SOCKETS TO BE SUPPLIED BY THE CONTRACTORS)	
	e) NECESSARY EARTH CONNECTIONS WITH METER AND METERING INSTALLATIONS.	
32	FIXING OF 1-PHASE ENERGY METER(STATIC/ELECTROMAGNETIC)WITH PILFER PROOF METER BOX WITH RELATED ASSOCIATED WORKS AS PER FOLLOWING SCHEDULE:	295.00
	a) FIXING OF 32 AMP CUTOUT 1 NO. WITH NECESSARY CONNECTION.	
	b) DRAWING AND FIXING OF L.T. PVC CABLE OF REQUISITE SIZE FROM SERVICE POLE TO METER BOX WITH SUPPLY AND FIXING CABLE GLAND MADE OF BRASS AND OF REQUISITE SIZE AND NECESSARY CONNECTIONS WITH ALUMINIUM SOCKETING (SOCKETS TO BE SUPPLIED BY THE CONTRACTORS)	
	c) NECESSARY EARTH CONNECTIONS WITH METER AND METERING INSTALLATIONS	
33	DISMATLING OF EXISTING 1 PHASE ENERGY MEER AND FIXING OF A NEW ONE WITH PILFER PROOF METER BOX AS PER THE FOLLOWING SCHEDULE:	454.00
	a) DISMATLING OF EXISTING OF 1.PHASE ENERGY METEER (STATIC/ELECTROMAGNATIQWITH ASSOCIATED INSTALLATIONS INCLUDING DISMANTLING OF BARE SERVICE LINE (I-PHASE)AND RETURNING THE SAME TO STORE.	
	b) FIXING OF 1-PHASE ENERGY METER (STATE/EKECTROMAGNETIC)WITH PILFER PROOF METER BOXfTO BE SUPPLIED BY THEBOARD)WITH RELATED ASSOCIATED WORKS	
	c) FIXING OF 32 AMP CUTOUT 1 NO WITH NECESSARY CONNECTIONS	
	d) DRAWING AND FIXING OF L.T. PVC CABVLE OF REQUESITE SIZE FROM SERVICE POLE TO METER BOX WITH SUPPLY AND FIXING CABLE GLAND MADE OF BRASS AND OF REQUISITE SIZE AND NECESSARY CONNECTIONS WITH ALUMINIUM SOCKETING (SOCKETS TO BE SUPPLIED BY THE CONTRACTORS)	
	e) NECESSARY EARTH CONNECTIONS WITH METER AND METERING INSTALLATIONS.	
34	RATE FOR EFFECTING DISCONNECTION/RECONNECTION OF SERVICE LINE FOR L&MV SUPPLY FOR COMMERCIAL AND DOMESTIC CONSUMERS	
	a) DISCONNECTION	
	i) SINGLE PHASE	65.00

ERECTION RATE FOR SPECIAL (O&M) WORK

SL NO	DESCRIPTION OF ITEM	RATE (in Rs.)
	ii) 3PHPHASE	88.00
	b) RECONNECTIION	
	i) SINGLE PHASE	65.00
	ii) 3PH PHASE	88.00
35	DISMATLING OF OLD/DEFECTIVE ENERGY METER AND FIXING OF A NEW ONE WITH PILFER PROOF METER BOX IN SAME PLACE WITH NECESSARY CONNECTIONS	
	i) SINGLE PHASE	153.00
	ii) 3PH PHASE	204.00
36	DISMATLING OF OLD DEFECTIVE ENERGY METER AND FIXING OF A NEW ONE WITHOUT PILFER PROOF METER BOX IN SAME PLACE WITH NECESSARY CONNECTIONS	
	i)SINGLE PHASE	122.00
	ii)3PH PHASE	153.00
37	WALK OVER SURVEY FOR IDENTIFICATION OF REMOTE VIRGIN MOUZAS (PER K.M.)	130.00
38	COST OF RETURNABLE DAMGED WOOD POLE. ERRECTED UNDER DIFERENT LOCATIONS IN THE FIELD.	402.00

ERECTION RATE FOR HT & LT AB CABLES

SLNO	DESCRIPTION OF ITEM	UNIT	RATE (in Rs.)
1	Stringing & sagging of 1.1 KVLT AB Cable on PCC pole average span of 25 m to 45 m with Fixing of Nylon Cable tie to be tied every' 2 mtr. interval of AB Cable with fixing of End caps at all open ends of AB Cable		
a	3 X 70+1 X 16 (Street Light) - 1 X 50 sq.mm (insulated messenger) AB Cable	Mtrs.	50.00
b	3 X 50+1 X 16 (Street Light) + 1 X 35 sq.mm (insulated messenger) AB Cable	Mtrs.	46.00
c	3 X 50+ 1 X 35 sq.mm. (insulated messenger) AB Cable	Mtrs.	29.00
2	Erection of Anchor Clamp suitable for LT AB Cable of 35/50 sq.mm Insulated Massenger, including Erection of G.I. Pole Clamp. G. I Flat type Eye Hook	No.	154.00
3	Erection of Suspension Clamp suitable for LT AB Cable of 35/50 sq.mm Insulated Massenger, including Erection of G.I. Pole Clamp, G. I Flat type Eye Hook	No.	154.00
4	Erection of Insulating Piercing Connectors for connection of Street Light including Connection wth AB Cable Size 16 sq.mm	No.	32.00
5	Erection of Insulating Piercing Connectors for connection of Distribution Boxes including Connection wth AB Cable	No.	32.00
6	Erection of Insulating Piercing Connectors for ABC tee Connection including Connection wth AB Cable	No.	32.00
7	Erection of distribution box install on pole by 2 nos Steel Strap & Buckles /GI Clamp.	No.	507.00
8	Erection of Pre-installcd Water proof Crimping type Sleeves for Straight though joints.	No.	106.00
9	Erection of Bimetallic Crimping Type water Proof lug for 16/50/70/35 mm LT Power Cable91 Set=4 nos)	No.	59.00
10 (a)	Dismantling of existing LT AB Cable,(3x 50 sq.mm.+ I x 35sq.mm + lxl6sq.mm,3 x 70sq.mm M x 50 sq.mm +1x16 sq.mm.,3 X 50+ 1 X 35 sq.mm.) connectors etc , and rewind inn in drums and return to store	Km	13.00
10 (b)	Dismantling of existing LT AB Cable,(3x 50 sq.mm. + 1 x 35sq.mm + lxl6sq.mm,3 x 70sq.mm - 1 x 50 sq.mm +1x16 sq.mm.,3 X 50+ 1 X 35 sq.mm.) connectors etc , and re-erection of cable at same location with necessary' fittings	Km	13.00
10 (c)	Re-Stringing &Re- sagging of existing 1.1 KVLT AB Cable(3x 50 sq.mm.+ 1 x 35sq.mm + lxl6sq.mm,3 x 70sq.mm + 1 x 50 sq.mm +1x16 sq.mm.,3 X 50+ 1 X 35 sq.mm.) with Fixing of Nylon Cable/f End caps at all open ends of AB Cable	Km	13.00
11	Replacement of damaged LT distribution box by new one	No.	440.00
12	Replacement of damaged Anchor Clamp/Suspension Clamp by new one.	No.	117.00
13	Stringing & sagging of 11KV HT AB Cable on PCC/RP pole average span of 25 m to 40 m(Max). With Fixing of Nylon Cable tie to be tied every 2 mtr. interval of AB Cable with fixing of End caps at all open ends of AB Cable		
a	3X95sqmm+l X 180sqmm 11 KV AB Cable	Mtrs.	48.00
b	3 X 50sq mm+ 1 XI05 sq.mm UKV AB Cable	Mtrs.	41.00
14	Erection of Anchor Clamp suitable for HT AB Cable of 105/180 sq.mm bare Massenger wire , including Erection of G.I./ M.S Pole Clamp, G. I/M.S Flat type Eye Hook	No.	259.00

ERECTION RATE FOR HT & LT AB CABLES

SLNO	DESCRIPTION OF ITEM	UNIT	RATE (in Rs.)
15	Erection of Suspension Clamp suitable for HT AB Cable of 105/180 sq.mm bare Massenger, including Erection of G.I/ M.S. Pole Clamp, G. I / M.S Flat type Eye Hook	No.	259.00
16 (a)	Dismantling of existing HT AB Cable(3 x 50 sq.mm.+ 1 x 105 sq.mm , 3 x 95 sq.mm f 1 x 180 sq.mm)and rewinding in drums and return to store	Km	21.00
16 (b)	Dismantling of existing HT AB Cable(3 x 50 sq.mm. - 1 x 105 sq.mm , 3 x 95 sq.mm + 1 x 180 sq.mm) and re-erection of cable at same location with necessary fittings.	Km	22.00
16 (c)	Re-Stringing &Re- sagging of existing 11 KV HT AB Cable (3 x 50 sq.mm.+ 1 x 105 sq.mm , 3 x 95 sq.mm + 1 x 180 sq.mm) with Fixing of Nylon Cable/f End caps at all open ends of AB Cable	Km	16.00
17	Replacement of damaged Anchor Clamp/Suspension Clamp by new one (HT).		293.00
18 (a)	Out door Termination of 1 x 50 sq.mm./1 x 95 sq.mm HT AB Cable by Heat Shrinkable jointing Kit. (ISet = 3 Nos)	Set	1272.00
18 (b)	Strainght through joint of HT (11 KV) AB Cable. Sizes 1 x 50 sq.mm./ 1 x 95 sq.mm HT AB Cable by FIcat Shrinkable jointing Kit. (1 Set - 3 Nos)	Set	1274.00
18 (c)	Tee Joint Tap of from HT ABC to DTR for 1CX95/ 1 x 50 sq.mm(store material) contains 2 nos. poly SA 1 No. 1.5m. Bus Tubing for 11 KV & 1 no Alumunium Busbar (ISet = 3 Nos)	Set	1281.00

SCHEDULE OF WORKS AND CORRESPONDING UNIT RATE FOR 11 KV & 11 KV UNDERGROUND ELECTRICAL SYSTEM WITHIN THE JURISDICTION OF WBSEDCL WITHIN WEST BENGAL EXCEPT HILLY AREA

Sl No	Description of Work	Unit	Rate (Rs.)	Remarks
1	Survey of H.T & L.T cable route as per instruction of Site Engineer and submission of route survey drawing (in two copies) inscribing different land marks	Mtr	2.70	
2	Excavation of soil for making of trial hole (Minm. Size 1.1 X 0.5 X 1.2M depth) as per instruction of the Site Engineer including backfilling the excavated soil.	Cum.	34.00	
3	Excavation of soil for formation of cable trenches & re-instatement of cable trenches with the excavated soil as per direction of Site Engineer.	Cum.	20.00	
4	Excavation of soil by cutting of Metalled Road/Cement Concrete/Brick Soling etc & re- instatement of the same as per instruction of Site Engineer	Cum.	152.00	
5	Excavation of soil along the existing cable route for formation of cable trenches along with the up-rooting of protective covers in the existing trenchs reinstatement of same cable trenches with the excavated soil after erection of protective covers.	Cum.	27.00	
6	Excavation of soil by cutting of Metalled Road/Cement Concrete/Brick massonry / chequered plate/ Paver block etc for formation of cable trench along with up-rooting of protective cover in the existing trench & reinstatement of the same cable trench after erection of protective cover.	Cum.	136.00	
7	Supply & laying of following R.C.C Spun Pipe (NP-3)			
i)	150mm dia. Spun Pipe	Mtr	557.00	
ii)	225mm dia. Spun Pipe.	Mtr	600.00	
8	Supply of kiln-burnt 1st class bricks having proper size & shape suitable for cable protective cover as per instruction of Site Engineer	No		See Annexure -"P"
9	Laying of bricks as per drawing and instruction of the Site Engineer	No.	1.12	
10	Laying & dressing of following 11 KV /1.1 KV PILC / XLPE/PVC cable in the excavated cable trenches as per drawing no.PLN(D)/SS/104, dt. 05.05.2015 and instruction of the Site Engineer.			
a	Cable 11 KV PILC / XLPE 3 x 35/50/70 sq. mm.	Mtr	35.00	
b	Cable 11 Ky PILC / XLPE 3 x 95/120 sq. mm.	Mtr	42.00	
c	Cable 11 KV PILC / XLPE 3 x 185/240 sq. mm.	Mtr	52.00	
d	Cable 11 KV PILC / XLPE 3 x 300/400 sq. mm	Mtr	62.00	
e	Cable 1.1 KVPVC/XLPE 2X10, 4X10/16, 3.5/4X25 sq. mm	Mtr	15.00	
f	Cable 1.1 KV PVC /XLPE 3.5/4 x 35/50/70 sq.mm	Mtr	24.00	
g	Cable 1.1 KVPVC /XLPE 3.5/4x95/120 sq.mm	Mtr	31.00	
h	Cable 1.1 KV PVC/XLPE 3.5/4 x 185 / 225/240 sq.mm	Mtr	39.00	
i	Cable 1.1 KVPVC/XLPE 3.5/4x300/400 sq.mm	Mtr	50.00	

SCHEDULE OF WORKS AND CORRESPONDING UNIT RATE FOR 11 KV & 11 KV UNDERGROUND ELECTRICAL SYSTEM WITHIN THE JURISDICTION OF WBSEDCL WITHIN WEST BENGAL EXCEPT HILLY AREA

Sl No	Description of Work	Unit	Rate (Rs.)	Remarks
11	Making of Straight Through/Transition Joint including making of jointing pit of the following 11/1. 1 KV.PILC/ XLPE/ PVC cable without supply of jointing materials excluding making of "protection duct for cable joint"			
a	Cable 11 KVPILC/XLPE 3x95/l20sq. mm.	No.	1604.00	
b	Cable 11 KV PILC / XLPE 3 x 185/240 sq. mm	No.	2037.00	
c	Cable 11 KV PILC / XLPE 3 x 300/400 sq. mm	No.	2150.00	
d	Cable 1.1 KV PVC/XLPE 2X10, 4X10/16, 3.5/4X25 sq. mm	No.	569.00	
e	Cable 1.1 KV PVC / XLPE 3.5/4 x 35/50/70 sq.mm	No.	576.00	
f	Cable 1.1 KV PVC / XLPE 3.5/4 x 95/120 sq.mm	No.	787.00	
g	Cable 1.1 KV PVC/ XLPE 3.5/4 x 185 / 225/240 sq.mm	No.	894.00	
h	Cable 1.1 KV PVC/ XLPE 3.5/4 x 300 / 400 sq.mm	No.	1027.00	
12	Making of T 'Joint /' T cum Straight Through' joint including making of jointing pit of the following 1.1 KV PVC/XLPE cable with jointing kit but without supply of jointing materials and excluding making of "protection duct for cable joint".			
a	Cable 1.1 KV PVC/XLPE 3.5/4x50 & 3.5/4 x 16 sq. mm	No.	689.00	
b	Cable 1.1 KV PVC/XLPE 3.5/4x 95 & 3.5/4 x 16 sq. mm	No.	1014.00	
c	Cable 1.1 KV PVC/XLPE 3.5/4x120 & 3.5/4 x 16 sq. mm	No.	1119.00	
d	Cable 1.1 KV PVC/XLPE 3.5/4 x 185 & 3.5/4 x 16 sq. mm	No.	1328.00	
e	Cable 1.1 KV PVC/XLPE 3.5/4 x 185 & 3.5/4 x 50 sq. mm	No.	1373.00	
13	Making & fixing of end termination joint indoor or outdoor type for 11 KV PILC /XLPE cable including fixing of the jointing box at the existing structure but without the jointing materials as per instruction of the Site Engineer.			
a	Cable 11 KV PILC / XLPE 3 x 95/120 sq. mm.	No.	1369.00	
b	Cable 11 KV PILC /XLPE 3 x 185/240 sq. mm	No.	1685.00	
c	Cable 11 KV PILC / XLPE 3 x 300/400 sq. mm	No.	2023.00	
14	Making of end termination of the following 1.1 KV PVC/ XLPE Cable excluding supply of suitable cable glands, tapes, lugs, sockets & other necessary materials as per instruction of the Site Engineer.			
a	Cable 1.1 KV PVC/XLPE 2 x 10/4X10/4 x 16/3.5x25sq. mm	No.	186.00	
b	Cable 1.1 KV PVC/XLPE 3.5/4 x 50 / 70 sq.mm.	No.	337.00	
c	Cable 1.1 KV PVC/XLPE 3.5/4 x 95/120 sq.mm.	No.	547.00	
d	Cable 1.1 KVPVC/XLPE 3.5/4 x 185/225 sq.mm.	No.	923.00	
e	Cable 1.1 KVPVC/XLPE 3.5/4 x300/400sg.mm..	No.	1144.00	
15	Making protective duct for cable joint complete as per WBSEDCLs approved drawing (Ref. Drg. no.PLN(D)/SS/106, dt. 05.05.2015)	No.	8991.00	

SCHEDULE OF WORKS AND CORRESPONDING UNIT RATE FOR 11 KV & 11 KV UNDERGROUND ELECTRICAL SYSTEM WITHIN THE JURISDICTION OF WBSEDCL WITHIN WEST BENGAL EXCEPT HILLY AREA

Sl No	Description of Work	Unit	Rate (Rs.)	Remarks
16	Supply & Erection of Cast Iron Cable Marker on concrete foundation blocks for straight run, road crossing, joint location etc as per drawing no..PLN(D)/SS/107 or 108, dt. 05.05.2015 & specification & direction of Site Engineer.	No.	300.00	
17	Supply & fixing/ laying of G.I Pipe (Medium) (Non-TATA) as per I.S.I of the following sizes suitable for cable protection as per instruction of Site Engineer.			
a	G.I Pipe 50mm dia. (Medium)	Mtr	461.00	
b	G.I Pipe 100mm dia.(Medium)	Mtr	777.00	
c	G.I Pipe 150 mm dia.(Medium)	Mtr	1152.00	
18	Making of R.C.C/ Cement Concrete/ Masonry Plinth/ Foundation suitable for the following items including supply of materials as per approved drawing .			
a	Distribution Transformer 630 KVA (Ref. Drg. no. PLN(D)/SS/101, dt. 05.05.2015)	No.	14758.00	
b	Distribution Transformer 315/250 KVA (Ref. Drg. no. PLN(D)/SS/101, dt. 05.052015)	No.	12049.00	
c	L&MV Kiosk (Ref. Drg. no. PLN(D)/SS/102, dt. 05.05.2015)	No.	10235.00	
d	Distribution Feeder Pillar Box . (Ref. Drg. no.PLN(D)/SS/102, dt. 05.05.2015)	No.	9237.00	
e	Block Junction Box / Plot Junction Box. (Ref. Drg. no. PLN(D)/SS/102, dt. 05.05.2015)	No.	4751.00	
f	Service Junction Box (Ref. Drg. no.PLN(D)/SS/102, dt. 05.05.2015)	No.	3676.00	
g	Street Light Feeder Pillar Box. (Ref. Drg. no. PLN(D)/SS/102, dt. 05.05.2015)	No.	3197.00	
h	Out Door 11 KV 250/ 350 MVA 400 / 630A, 3 /4 Way RMU (Ref. Drg. no. PLN(D)/SS/132 & 133, dt. 17.06.2019)	No.	24065.00	
i	Out Door 11 KV 250/ 350 MVA 400 / 630A, 3 /4 Way RMU with FRTU (Ref. Drg. no. PLN(D)/SS/137 , dt. 04.07.2019)	No.	28887.00	
19	Erection of the following items on the existing plinth / structure including proper fixing on the plinth / Structure as per instruction of the Site Engineer.			
a	Distribution Transformer 630 KVA	No.	14433.00	
b	Distribution Transformer 315/250 KVA	No.	7248.00	
c	L& MV Kiosk	No.	1441.00	
d	Distribution Feeder Pillar Box .	No.	1499.00	
e	Block Junction Box/Service Junction Box.	No.	696.00	
f	Street Light Feeder Pillar Box.	No.	897.00	
g	L& MV metering Kiosk (L.T Bulk Consumer)	No.	2155.00	

SCHEDULE OF WORKS AND CORRESPONDING UNIT RATE FOR 11 KV & 11 KV UNDERGROUND ELECTRICAL SYSTEM WITHIN THE JURISDICTION OF WBSEDCL WITHIN WEST BENGAL EXCEPT HILLY AREA

Sl No	Description of Work	Unit	Rate (Rs.)	Remarks
20	Earthing of Transformer / Indoor or out door 3 or 4 way RMU /Single or Multi 11 KV OCB / VCB as per drawing consisting of 1 nos, 3 metres long 50 mm dia. medium gauge G.I TATA make Pipe (M), installation & connection in between earth pipe and other equipments using 2 nos. G,I Flat 40mm x 6 mm. by welding complete and as per instruction of the Site Engineer (including supply of all materials)	Job	5038.00	
21	Erection of Indoor 11 KV 250 /350 MVA 400 /630 A 3 way Ring Main Unit, metering / non-metering OCB/VCB complete as per WBSEDCL's approved drawing and as per instruction of Site Engineer.	Set	10626.00	
22	Erection of Out Door 11 KV 250/ 350 MVA 400 / 630A 3 way RMU metering /non-metering OCB / VCB complete on existing plinth as per WBSEDCL's approved drawinq and as per instruction of Site Engineer.	Set	9787.00	
23	Erection of Indoor 11 KV 250 /350 MVA 400 /630 A 4 way Ring Main Unit. metering / non-metering OCBA/CB complete as per WBSEDCL's approved drawinq and as per instruction of Site Engineer.	Set	12372.00	
24	Erection of Out Door 11 KV 250/ 350 MVA 400 / 630A 4 way RMU metering /non-metering OCB / VCB complete on existing plinth as per WBSEDCL's approved drawinq and as per instruction of Site Engineer.	Set	11532.00	
25	Erection of Shunt / Series Trip Indoor type 11 kV. 250/350MVA. 400/ 800/1250 Amp. metering /non-metering OCB / VCB complete as per WBSEDCL's approved drawinq and as per instruction of Site Engineer.	No.	6628.00	
26	Drying out of 11 KV 3/4 Way Ring Main Unit / Single panel metering / non metering OCB / VCB including CT. PT etc for improving of insulation value up to the suitable limit and as per instruction of the Site Engineer.	Set	928.00	
27	Special arrangement for covering of the 11 KV end jointing portion at the 11 KV Isolator or OCB / VCB end by using M.S. Sheet 10 Gauge M.S Angle etc. as per instruction of the Site Engineer including supply of all materials & with paints.	No.	1698.00	
28	Extension of cable end jointing box of the Transformer, H.V side with M.S. Sheet. Angles etc. suitable for fixing & covering of the 11 KV end joint as per instruction of Site Engineer.	No.	1698.00	
29	De-compounding, of existing 11 KV cable end joint box & cleaning of the box suitable for further use of the said box as per instruction of the Site Engineer.	No.	1054.00	

SCHEDULE OF WORKS AND CORRESPONDING UNIT RATE FOR 11 KV & 11 KV UNDERGROUND ELECTRICAL SYSTEM WITHIN THE JURISDICTION OF WBSEDCL WITHIN WEST BENGAL EXCEPT HILLY AREA

Sl No	Description of Work	Unit	Rate (Rs.)	Remarks
30	Making of jointing pit only by the excavation of soil suitable for making of straight through joint of following cables including laying of platform with bricks for placement of joint box & pitching up of temporary tent by providing bamboo & tarpolene & re-instatement, of the joint pit with the excavated soil after completion of jointing work			
a	11KV	No.	998.00	
i)	1.1 KV	No.	368.00	
31	Lifting & checking of the following 11 KV / 1.1 KV PILC / XLPE / PVC cable to ascertain the actual fault including guarding arrangement up to the time of testinq & jointing works			
a	Cable 11 KV PILC / XLPE 3 x 35/50/70 sq. mm	Mtr.	25.00	
b	Cable 11 KV PILC / XLPE 3 x 95/120 sq. mm.	Mtr	29.00	
c	Cable 11 KV PILC / XLPE 3 x 185/240 sq. mm.	Mtr	38.00	
d	Cable 11 KV PILC / XLPE 3 x 300/400 sq. mm.	Mtr	46.00	
e	Cable 1.1 KV PVC/XLPE 2x10, 3.5/4X10, 3.5/4 x 16, 3.5/4 X 25 sq mm	Mtr	17.00	
f	Cable 1.1 KV PVC/ XLPE 3.5/4 x 35/50 / 70 sq. mm.	Mtr	29.00	
g	Cable 1.1 KV PVC / XLPE 3.5/4x 95 /120 sq. mm.	Mtr	34.00	
h	Cable 1.1 KV PVC / XLPE 3.5/4 x 185 / 225 /240 sq. mm.	Mtr	36.00	
i	Cable 1.1 KV PVC/XLPE 3.5/4 x 300/400 sq. mm.	Mtr	50.00	
32	Relaying & dressing of existing healthy portion of the following 11 KV/ 1.1 KV PILC / XLPE / PVC cable in the already excavated trench as per instruction of the Site Engineer.			
a	Cable 11 KV PILC / XLPE 3 x 95/120 sq. mm.	Mtr	31.00	
b	Cable 11 KV PILC / XLPE 3 x 185/240 sq. mm.	Mtr	35.00	
c	Cable 11 KV PILC / XLPE 3 x 300/400 sq. mm.	Mtr	43.00	
d	Cable 1.1 KV PVC/XLPE 2x10, 3.5/4X10, 3.5 /4 x 16, 3.5/4 x 25 sq mm	Mtr	15.00	
e	Cable 1.1 KV PVC/ XLPE 3.5/4 x 35/50 / 70 sq. mm.	Mtr	21.00	
f	Cable 1.1 KV PVC/XLPE 3.5/4x95/120 sq. mm.	Mtr	27.00	
g	Cable 1.1 KV PVC/XLPE 3.5/4 x 185 / 225/240 sq. mm.	Mtr	31.00	
h	Cable 1.1 KV PVC/ XLPE 3.5/4 x 300 / 400 sq. mm.	Mtr	42.00	
33	Dismantling of the following worn-out / damage/ good items from the existing plinth including return to store.			
a	L & MV Kiosk / Feeder Filler Box.	No.	797.00	
b	S.J.B/J.B / Street light feeder Pillar Box	No.	587.00	
34	Demolishing of the existing plinth including removal of debris from work site.			
a	L&MV Kiosk/ Feeder Pillar Box (As per drg. no. PLN(D) /SS/102, dt. 05.05.2015)	No.	860.00	
b	S.J.B/J.B / Street light feeder Pillar Box (As per drg. no. PLN(D)/SS/102, dt. 05.05.2015)	No.	410.00	

SCHEDULE OF WORKS AND CORRESPONDING UNIT RATE FOR 11 KV & 11 KV UNDERGROUND ELECTRICAL SYSTEM WITHIN THE JURISDICTION OF WBSEDCL WITHIN WEST BENGAL EXCEPT HILLY AREA

Sl No	Description of Work	Unit	Rate (Rs.)	Remarks
35	Fitting & fixing of following items with / without fabrication complete in all respect in L&MV panel /FP box/JB/SJB/ Street light feeder pillar box, Consumer's premises as oer instruction of Site Engineer.			
a	MCCBs of rating 400 A and above	No.	928.00	
b	Main Switches of rating 200 A and above	No.	1138.00	
c	Cut-out of rating 200A and above complete set.	No.	442.00	
d	Cut-out of rating 100 A and below complete set.	No.	232.00	
36	Dismantling of the following items from L & MV panel / feeder pillar box / Junction Box / Service Junction Box / Consumer's premises as per instruction of Site Engineer.			
a	MCCBs of rating 400 A and above	No.	337.00	
b	Main Switches of rating 200 A and above	No.	295.00	
c	Cut-out of rating 200A and above complete set.	No.	189.00	
d	Cut-out of rating 100 A and below complete set.	No.	74.00	
37	Supply & installation of earth Bus-bar made of galvanized iron of size 600 mm x 25 mm x 4mm with 5 nos of holes with necessary bending and fixing on the wall.	No.	360.00	
38	Supply & fixirfg of cable tag on the cable.	No.	48.00	
39	Dismantling of 11 KV 250 /350 .MVA, 400 / *630* A 3- Way Indoor/ Out Door Ring Main Unit with 2 Incoming with metering/ Non- Metering OCB / VCB with accessories and return the same to WBSEDCL's Store including transportation charges	Set	4794.00	
40	Dismantling of 11 KV Single panel 250 /350 MVA. 400 / 800/ 1250 A Shunt / Series Trip Indoor type metering OCB / VCB with accessories and return the same to WBSEDCL's Store including transportation charges.	Set	3447.00	
41	Removal/ Uprooting & Returning of 11 KV XLPE / PILC cable from site to WBSEDCL's Store includinq transportation charqes.			
a	3x *35* sqmm. & up to 120 sq.mm. cable	Mtr	31.00	
b	3x 150 sqmm. & up to 240 sq.mm cable	Mtr	35.00	
c	3x 300sqmm. & up to 400sq.mm cable	Mtr	43.00	
42	Removal/ Uprooting of 11 KV XLPE / PILC cable from the existing cable trenches including protective covers(bricks) by excavation of soil and shifting & relaying the same cable in the new cable trenches by excavation of soil and installation of cable protective covers (existing bricks) and re-instatement of the same cable trenches with the excavated soil as per instruction of the Site Engineer			
a	3x 35 sqmm. & up to 120 sq.mm. cable	Mtr	77.00	
b	3x 150 sqmm & up to 240 sq.mm cable	Mtr	89.00	
c	3x 300sqmm. & up to 400sq.mm cable	Mtr	117.00	

SCHEDULE OF WORKS AND CORRESPONDING UNIT RATE FOR 11 KV & 11 KV UNDERGROUND ELECTRICAL SYSTEM WITHIN THE JURISDICTION OF WBSEDCL WITHIN WEST BENGAL EXCEPT HILLY AREA

Sl No	Description of Work	Unit	Rate (Rs.)	Remarks
43	Removal/Uprooting & Returning of 1.1 KV XLPE/ PVC cable from site to WBSEDCLs Store including transportation charges as per instruction of the Site Engineer.			
a	2X10, 4X10. 4X16, 3.5/4 X 25sq.mm	Mtr	8.00	
b	3.5/4 X 35/50/70 sq. mm	Mtr	10.00	
c	35/4X95/120 sq.mm	Mtr	13.00	
d	35/4 X 185 / 225 / 240 sq.mm	Mtr	15.00	
e	35/4X300/400sq. mm	Mtr	17.00	
44	Removal/Uprooting of existing 1.1 KV XLPE / PVC cable from the existing cable trenches and shifting and relaying the same cable in the new cable trenches as per instruction of the Site Engineer.			
a	2X10. 4X10, 4X16, 3.5/4X25 sq.mm	Mtr	8.70	
b	3.5/4 x 35 / 50 / 70 / 90 /120 sq.mm	Mtr	73.00	
c	3.5/4 x 150/185/240 sq.mm	Mtr	94.00	
d	3 .5/4x300/400 sq.mm	Mtr	110.00	
45	Making of end termination in one lead/one phase of the following 1.1 KV PVC/ XLPE Cable including supply of suitable cable glands as per instruction of the Site Engineer.			
a	Cable 1.1 KV PVC/ XLPE 3.5/4 x 50/70 sq.mm	No.	74.00	
b	Cable 1.1 KV PVC/ XLPE 3.5/4 x 95 /120 sq.mm.	No.	146.00	
c	Cable 1.1 KV PVC/XLPE 3.5/4 x 185 / 225 sq.mm. .	No.	229.00	
d	Cable 1.1 KV PVC/ XLPE 3.5 /4 x 300 / 400 sq.nim.	No.	271.00	
46	De-compounding of existing 1.1 KV grade cable end joint box & cleaning of the box suitable for further use of the said box as per instruction of the Site Engineer	No	420.00	
47	Micro-Tunnelling work with laying of HDPE pipe as per instruction of Site Engineer and as per site condition with laying of U.G cable including supply of HDPE pipe as per IS: 4984-1995 including preparation and submission of drawing for such cable laying			Detail scope of Micro-Tunnelling work is as per Annexure- "S"
a	With 160mm diam. HDPE Pipe, PE-80 , PN-6 (this rate is applicable for state highway/NH/Road with propensity of high density of heavy vehicle)	Mtr	1588.00	
b	With 110mm diam. HDPE Pipe,PE-80 , PN-6 (this rate is applicable for state highway/NH/Road with propensity of high density of heavy vehicle)	Mtr	1116.00	
48	Micro-Tunnelling work with laying of HDPE pipe as per instruction of Site Engineer and as per site condition with laying of U.G cable including supply of HDPE pipe as per IS: 4984-1995 including preparation and submission of drawing for such cable laying			Detail scope of Micro-Tunnelling work is as per Annexure- "S"
a	With 160mm diam. HDPE Pipe, PE-80 , PN-4 (this rate is applicable for Normal road / Normal corridor)	Mtr	1323.00	
b	With 110mm diam. HDPE Pipe,PE-80 , PN-4 (this rate is applicable for Normal road / Normal corridor)	Mtr	987.00	

SCHEDULE OF WORKS AND CORRESPONDING UNIT RATE FOR 11 KV & 11 KV UNDERGROUND ELECTRICAL SYSTEM WITHIN THE JURISDICTION OF WBSEDCL WITHIN WEST BENGAL EXCEPT HILLY AREA

Sl No	Description of Work	Unit	Rate (Rs.)	Remarks
49	Laying of HDPE pipe as per Jack push method as per instruction of Site Engineer and as per site condition for laying of U.G cable including supply of HDPE pipe as per IS: 4984-1995			Detail scope of Micro-Tunnelling work is as per Annexure- "S"
a	With 160mm diam. HDPE Pipe, PE-80 , PN-6	Mtr	1320.00	
b	With 110mm diam. HDPE Pipe, PE-80 , PN-6	Mtr	1045.00	
50	Laying of 11 KV. XLPE/ PILC U.G cable as per specification and as per approved drawing no. PLN(D)/SS/105. dt. 05.05.2015 and instruction of Site Engineer			
a	Double cable in a trench			
	i. Cable size 185 sqmm. & below	Mtr	70.00	
	ii. Cable size 240 sqmm. & above	Mtr	90.00	
b	More than 2 cables in a trench			
	i. Cable size 185 sqmm. & below	Mtr	107.00	
	ii. Cable size 240 sqmm. & above	Mtr	129.00	
51	Laying of 1.1 KV. XLPE/ PVC U.G cable as per specification and as per approved drawing no. PLN(D)/SS/105. dt. 05.05.2015 and instruction of Site Engineer			
a	Double cable in a trench			
	i. Cable size 185 sqmm. & below	Mtr	57.00	
	ii. Cable size 240 sqmm. & above	Mtr	72.00	
b	More than 2 cables in a trench			
	i. Cable size 185 sqmm. & below	Mtr	82.00	
	ii. Cable size 240 sqmm. & above	Mtr	102.00	

Annexure "P"

Rates of supply of 1st Class Bricks (Kiln Burnt) in different Districts of West Bengal as per PWDSOR'2017 (Ref: item no 8 of "RATE CONTRACT" of UG Cable)

Sl no	Name of the District	Unit	Rate (Rs.)
1	Kolkata/ 24- Parganas (S)/ 24- Parganas (N)/ Howrah/ Hooghly/Area of Kalyani Sub Div	1000 nos.	8095.00
2	Burdwan(Purba & Paschim)	1000 nos.	7381.00
3	Purulia/ Birbhum	1000 nos.	6190.00
4	Midnapur(E)/ Midnapur(W)/Jhargram	1000 nos.	8095.00
5	Bankura	1000 nos.	6762.00
6	Nadia (excluding the Area of Kalyani Sub Div)/ Murshidabad	1000 nos.	7381.00
7	Malda	1000 nos.	7381.00
8	Jalpaiguri/Alipurduar/ Plains of Siliguri Sub Div/ Haldibari P.S	1000 nos.	7381.00
9	Coochbehar excluding the area of Haldibari PS	1000 nos.	7381.00
10	Uttar Dinajpur/ Dakshin Dinajpur	1000 nos.	7381.00
11	Darjeeling,Kalingpong except plains of siliguri sub Divn	1000 nos.	10000.00

SCHEDULE OF WORKS AND CORRESPONDING UNIT RATE FOR 33 KV UNDERSROUND ELCTRICAL SYSTEM WITHIN THE JURISDICTION OF WBSEDCL WITHIN WEST BENGAL EXCEPT HILLY AREA				
Sl. No.	**Description of work**	**Unit**	**RATE (RS)**	**Remarks**
1	Survey of H.T & L.T cable route as per instruction of Site Engineer and submission of route survey drawing (in two copies) inscribing different land marks	Mtr	3.00	
2	Excavation of soil for making of trial hole (Minm. Size 1.1 X 0.5 X 1.2M depth) as per instruction of the Site Engineer including backfilling the excavated soil.	Cum.	34.00	
3	Excavation of soil for formation of cable trenches & re-instatement of cable trenches with the excavated soil as per direction of Site Engineer.	Cum.	21.00	
4	Excavation of soil by cutting of Metalled Road/Cement Concrete/Brick Soling etc & re-instatement of the same as per instruction of Site Engineer	Cum.	154.00	
5	Excavation of soil along the existing cable route for formation of cable trenches along with the up-rooting of protective covers in the existing trench & reinstatement of same cable trenches with the excavated soil after erection ol protective covers.	Cum.	27.00	
6	Excavation of soil by cutting of Metalled Road/Cement Concrete/Brick massonry / chequered plate/ Paver block etc for formation of cable trench along with uprooting of protective cover in the existing trench A reinstatement of the same cable trench after erection of protective cover.	Cum.	138.00	
7	Supply & laying of following R.C.C Spun Pipe (NP-3)			
a	150mm dia. Spun Pipe	Mtr	557.00	
b	225mm dia. Spun Pipe	Mtr	600.00	
8	Supply of kiln-burnt 1st class bricks having proper size A shape suitable for cable arotective cover as per instruction of Site Engineer	No	See Annexure "P"	As per Annexure-P
9	Laying of bricks as per drawing and instruction of the Site Engineer	No.	1.12	
10	Laying & dressing of following 33 KV XLPE cable in the excavated cable trenches is per drawing no. PLN(D)/SS/126, dt. 23.06.2018 and instruction of the Site Engineer.			
a	Cable 33 KV XLPE 3 x 185/240 sq. mm.	Mtr	65.00	
b	Cable 33 KV XLPE 3 x 300/400 sq. mm	Mtr	75.00	
11	Making of Straight Through/Transition Joint including making of jointing pit of he following 33 KV XLPE cable without supply of jointing materials excluding naking of "protection duct for cable joint"			
a	Cable 33 KV XLPE 3 x 185/240 sq. mm	No.	2266.00	
b	Cable 33 KV XLPE 3 x 300/400 sq. mm	No.	2377.00	
12	Making & fixing of end termination joint indoor or outdoor type for 33 KV XLPE cable including fixing of the jointing box at the existing structure but without the jointing materials as per instruction of the Site Engineer.			
a	Cable 33 KV XLPE 3 x 185/240 sq. mm	No.	1880.00	
b	Cable 33 KV XLPE 3 x 300/400 sq. mm	No.	2200.00	
13	Making protective duct for cable joint complete as per WBSEDCLs approved No. drawing (Ref. Drg. no. PLN(D)/SS/127, dt. 23.06.2018)		9154.00	
14	Supply & Erection of Cast Iron Cable Marker on concrete foundation blocks for straight run, road crossing, joint location etc as per drawing no. PLN(D)/SS/128 dt. 23.06.2018 & specification & direction of Site Engineer.	No.	300.00	
15	Supply & fixing/ laying of G.I Pipe (Medium) as per I.S.I of the following sizes suitable for cable protection as per instruction of Site Engineer.			
a	G.I. Pipe 150 mm dia. (Medium) TATA	Mtr	1360.00	
b	G.I Pipe 200 mm dia. (Medium) TATA/JINDAL/ EQUIVALENT	Mtr	2077.00	

Sl. No.	Description of work	Unit	RATE (RS)	Remarks
16	Making of jointing pit only by the excavation of soil suitable for making of 33 KV straight through joint of following cables including laying of platform with bricks for placement of joint box & pitching up of temporary tent by providing bamboo & tarpolene & re-instatement, of the joint pit with the excavated soil after completion of jointing work	No.	1007.00	
17	Lifting A checking of the following 33 KV XLPE cable to ascertain the actual fault including guarding arrangement Up to the time of testing & jointing works			
a	Cable 33 KV XLPE 3 x 185/240 sq. mm.	Mtr	48.00	
b	Cable 33 KV XLPE 3 x 300/400 sq. mm.	Mtr	56.00	
18	Relaying A dressing of existing healthy portion of the following 33 KV XLPE cable in the already excavated trench as per instruction of the Site Engineer.			
a	Cable 33 KV XLPE 3 x 185/240 sq. mm.	Mtr	44.00	
b	Sable 33 KV XLPE 3 x 300/400 sq. mm.	Mtr	52.00	
19	Removal/ Uprooting & Returning of 33 KV XLPE cable from site to WBSEDCL's Store including transportation charges.			
a	3x180sqmm & up to 240 sq.mm cable	Mtr	44.00	
b	3x300sqmm & up to 400sq.mm cable	Mtr	51.00	
20	Micro-Tunnelling work with laying of HDPE pipe as per instruction of Site Ingineer and as per site condition for laying of U.G. cable including supply of HDPE pipe as per IS: 4984-1995 including preparation and submission of drawing for such cable laying			Detail scope of Micro-Tunnelling work is as per Annexure- "S"
a	With 160mm dia. HDPE Pipe of PE-80, PN-6	Mtr	1980.00	
b	With 200mm dia. HDPE Pipe of PE-80, PN-6	Mtr	2419.00	
21	Laying of HDPE pipe as per Jack push method as per instruction of Site Engineer and as per site condition for laying of U.G. cable including supply of HDPE pipe as per IS: 4984-1995			
a	With 160mm dia. HDPE Pipe of PE-80 , PN-6	Mtr	1320.00	
b	With 200mm dia. HDPE Pipe of PE-80, PN-6	Mtr	2136.00	
22	Laying of G.I. pipe as per Jack push method as per instruction of Site Engineer and as per site condition for laying of U.G. cable including supply of G.I pipe as per IS: 4984-1995 specially in rail crossing.			t
a	With 150mm diam. G.I. Pipe TATA	Mtr	1849.00	
b	With 200mm diam. G.I. Pipe TATA / JINDAL / EQUIVALENT	Mtr	2560.00	
23	Laying of 33 KV, XLPE U.G Double cable in a trench as per specification and as per approved drawing no. PLN(D)/SS/126, dt. 23.06.2018 and instruction of Site Engineer			
a	Cable size 185 /240 sqmm.	Mtr	95.00	
b	Cable size 300/400 sqmm.	Mtr	117.00	

Annexure -"P"

Rates of supply of 1st Class Bricks (Kiln Burnt) in different Districts of West Bengal. as per PWDSOR'2014 (Ref:- item no. 8 of "RATE CONTRACT" of U.G Cable)			
Sl. No.	**Name of the District**	**Unit**	**Rate (Rs.)**
1	Kolkata/ 24- Parganas (S)/ 24-Parganas (N)/ Howrah/ Hooghly/Area of Kalyani Sub Div	1000 nos.	8095.00
2	Burdwan(Purba & Paschim)	1000 nos.	7381.00
3	Purulia/ Birbhum	1000 nos.	6190.00
4	Midnapur(E)/Midnapur(W)/Jhargram	1000 nos.	8095.00
5	Bankura I	1000 nos.	6762.00
6	Nadia (excluding the Area of Kalyani Sub Div)/ Murshidabad	1000 nos.	7381.00
7	Malda	1000 nos.	7381.00
8	Jalpaiguri/ Alipur^uar/ Plains of Siliguri Sub Div / Haldibari P.S	1000 nos.	7381.00
9	Coochbehar excluding the area of Haldibari PS	1000 nos.	7381.00
10	Uttar Dinajpur/ Dakshin Dinajpur	1000 nos.	7381.00

MATERIAL COST DATA (2021-22)

SL	MAT_CODE	DESCRIPTION OF MATERIALS	UNIT	GST	COST (IN RS)
POLE SECTION					
1	0110030141	PCC POLE : 8M LONG	NO	18%	3942.64
2	0110030241	PCC POLE : 9M LONG	NO	18%	7663.31
3	0110010341	STEEL TUBULAR POLE 9 M LONG (WITH CAP)	NO	18%	9783.57
4	0110010741	STEEL TUBULAR POLE 11 M LONG (WITH CAP)	NO	18%	15624.51
5	0110020711	RAIL POLE (11-13 M LONG) 52 KG	MT	18%	73630.83
6	0110050911	STEEL BEAM (JOIST) 11 M LONG, 37.1 KG/MT, HOT ROLLED WITHOUT GALVANIZATION	MT	18%	56788.56
7	0110051011	STEEL BEAM (JOIST) 13 M LONG, 37.1 KG/MT, HOT ROLLED WITHOUT GALVANIZATION	MT	18%	56788.56
8	0110051111	WIDE FLANGE BEAM 11 M LONG WBP 160X160X30.44 KG/M WITH GRADE E300	MT	18%	67112.64
9	0110051211	WIDE FLANGE BEAM: 13 M LONG WBP 160X160X30.44 KG/M WITH GRADE E300	MT	18%	69749.39
STEEL SECTION					
10	0102010911	M.S CHANNEL 100X50MM	MT	18%	73337.03
11	0102010611	M.S CHANNEL 75X40 MM	MT	18%	76451.71
12	0101011311	M.S.ANGLE 65X65X6 MM	MT	18%	72281.36
13	0101011011	M.S ANGLE 50X50X6 MM	MT	18%	73741.59
14	0103011211	M.S FLAT 50X6 MM	MT	18%	79505.78
15	0103011511	M.S FLAT 65X6 MM	MT	18%	79505.78
16	0103011611	M.S FLAT 65X8 MM	MT	18%	78721.21
17	0103011911	MS FLAT 75X8 MM	MT	18%	78721.21
18	0103012311	M.S FLAT 75X12 MM	NOS	18%	78721.21
STAY SET					
19	0504130432	G.I. STAY SET HT(1830X20MM)WRKG LD 7900KG	NOS	18%	968.14
20	0504130332	G.I. STAY SET LT(1680X16MM)WRKG LD-5100KG	NOS	18%	551.97
EARTH SPIKE					
21	0504110541	G.I. EARTH SPIKE 1833X20MM	NOS	18%	403.03
G I. WIRE					
22	0503010411	G.I. WIRE: 0.91 MM	MT	18%	101756.15
23	0503010611	G.I. WIRE : 3.15 MM	MT	18%	101194.21
24	0503010711	G.I. WIRE 4 MM	MT	18%	99733.97
25	0503010811	G.I. WIRE 5 MM	MT	18%	98711.81
G.I. STAY WIRE					
26	0503050911	G.I. STAY WIRE 7/4 MM (8 SWG)	MT	18%	103384.56
27	0503050711	G.I. STAY WIRE 7/3.15MM (10 SWG)	MT	18%	104552.74
28	0503050611	G.I STAY WIRE 7/2.SMM (12 SWG)	MT	18%	107035.14
29	0503050311	G.I. STAY WIRE 3/2.5MM (12 SWG)	MT	18%	101740.18
G.I. PIN FOR PORCELAIN INSULATOR					
30	0504110441	G I PIN FOR 33KV PORCELAIN PIN INSULATOR	NO	18%	261.18
31	0504111341	G I PIN FOR 11KV PORCELAIN PIN INSULATOR	NO	18%	91.05
33 KV PORCELAIN INSULATOR					
32	508010741	33KV PORCELAIN PIN INSULATOR (10KN- 580MM CREEPAGE DISTANCE)	NOS	18%	423.32

MATERIAL COST DATA (2021-22)

SL	MAT_CODE	DESCRIPTION OF MATERIALS	UNIT	GST	COST (IN RS)
33	0508010841	33KV PORCELAIN PIN INSULATOR (10KN- 840MM CREEPAGE DISTANCE)	NOS	18%	951.89
34	508020432	33KV PORCELAIN POST INSULATOR (STACK TYPE)	SO	18%	1022.17

33 KV POLYMER INSULATOR

35	0508011041	33 KV POLYMER COMPOSITE WITH FITTINGS PIN INSULATOR (10KN- 900MM CREEPAGE DISTANCE)	NOS	18%	502.18
36	0508030641	33 KV POLYMER COMPOSITE WITH FITTINGS 70KN DISC INSULATOR	NOS	18%	302.27

11 KV PORCELAIN INSULATOR

37	0508010341	11KV PORCELAIN PIN INSULATOR (5KN- 230MM CREEPAGE DISTANCE)	NOS	18%	68.26
38	0508010441	11KV PORCELAIN 320MM CD PIN INSULATOR (5KN- 320MM CREEPAGE DISTANCE)	NOS	18%	103.83
39	0508030441	11KV PORCELAIN 70KN DISC INSULATOR	NO	18%	418.53
40	0508030741	11KV PORCELAIN 120KN DISC INSULATOR	NO	18%	741.21
41	0508030341	11KVPORCELAIN 45KN DISC INSULATOR	NO	18%	359.42
42	0508020341	11KV PORCELAIN POST INSULATOR	NO	18%	278.33

11 KV POLYMER INSULATOR

43	0508011141	11 KV POLYMER COMPOSITE WITH FITTINGS PIN INSULATOR (5KN-320MM CREEPAGE DISTANCE)	NOS	18%	223.42
44	0508030541	11 KV POLYMER COMPOSITE 45KN DISC INSULATOR	NOS	18%	169.35

COMBINED HARDWARE FITTINGS

45	504010132	COMPOSITE HARDWARE FITTINGS FOR ACSR WEASEL/ RABBIT (30/50 SQMM)CONDUCTOR	SET	18%	248.83
46	0504010232	COMPOSITE HAROWARE FITTINGS SUITABLE FOR ACSR DOG (100 SQMM)CONDUCTOR	SET	18%	365.79
47	0504010332	SINGLE TENSION HARDWARE FITTINGS FOR ACSR WOLF (150 SQMM) CONDUCTOR	SET	18%	1026.55
48	0504010432	SINGLE SUSPENSION HARDWARE FITTINGS FOR ACSR WOLF (150 SQMM) CONDUCTOR	SET	18%	456.47
49	0504010532	SINGLE TENSION HARDWARE FITTINGS FOR PANTHER (200 SQMM) CONDUCTOR	SET	18%	1274.79
50	0504010632	SINGLE SUSPENSION HARDWARE FITTINGS FOR PANTHER (200 SQMM) CONDUCTOR	SET	18%	522.76

LIGHTNING ARRESTER

51	0309010541	LIGHTNING ARRESTER 42KV 10 KA PORCELAIN HOUSED GAPLESS TYPE FOR 33KV SYSTEM	NO	18%	6965.32
52	0309010841	LIGHTNING ARRESTER 12 KV 5KA PORCELAIN HOUSED GAPLESS TYPE FOR 11KV SYSTEM	NO	18%	459.98

11 KV ISOLATOR

53	0304010632	TPGO ISOLATOR : 11 KV : 400 AMP	SET	18%	15770.53
54	0304010532	TPGO ISOLATOR : 11 KV : 200 AMP	SET	18%	8250.33

33 KV ISOLATOR

55	0304010332	33 KV 400 A TPGO ISOLATOR (ROCKING TYPE)	SET	18%	40318.52
56	0304022332	33 KV 400 A CR TYPE ISOLATOR WITHOUT EARTH SWITCH (HIGH LEVEL)	SET	18%	33147.31
57	304020832	33 KV 400 A CR TYPE ISOLATOR WITHOUT EARTH SWITCH (LOW LEVEL)	SET	18%	32855.26

MATERIAL COST DATA (2021-22)

SL	MAT_CODE	DESCRIPTION OF MATERIALS	UNIT	GST	COST (IN RS)
58	304021132	33 KV 400 A CR TYPE ISOLATOR WITH EARTH SWITCH (HIGH LEVEL)	SET	18%	41908.71

ACSR CONDUCTOR

59	0502010321	ACSR SQUIRREL (20 SQMM) CONDUCTOR	KM	18%	16868.17
60	0502010621	ACSR WEASEL (30SQMM) CONDUCTOR	KM	18%	22893.51
61	0502010921	ACSR RABBIT (50 SQMM) CONDUCTOR	KM	18%	38676.40
62	0502011221	ACSR DOG (100 SQMM) CONDUCTOR	KM	18%	75557.91
63	0502011521	ACSR WOLF (150 SQMM) CONDUCTOR	KM	18%	141548.63
64	0502011821	COND ACSR PANTHER 200 SQMM	KM	18%	196213.08

PVC CABLE, 1.1 KV GRADE

65	0501012921	CABLE(PVC 1.1 KV GRADE) 2CX4 SQMM	KM	18%	23907.77
66	0501013021	CABLE(PVC 1.1 KV GRAOE) 2CX6 SQMM	KM	18%	25284.26
67	0501017421	CABLE(PVC 1.1 KV GRADE) 4CX10 SQMM	KM	18%	77965.35
68	0501017721	CABLE(PVC 1.1 KV GRADE) 4CX16 SQMM .	KM	18%	119154.63
69	0501017821	CABLE(PVC 1.1 KV GRADE) 4CX25 SQMM	KM	18%	127038.88
70	0501017921	CABLE (PVC 1.1 KV GRADE) 4CX50 SQMM	KM	18%	216551.21
71	0501018121	CABLE(PVC 1.1 KV GRADE) 4CX120 SQMM	KM	18%	425621.05
72	0501018221	CABLE(PVC 1.1 KV GRADE) 4CX185 SQMM	KM	18%	676430.17
73	0501018321	CABLE(PVC 1.1 KV GRADE) 4CX300 SQMM	KM	18%	985219.73

1.1 KV GRADE XLPE CABLE

74	0501020321	CABLE(XLPE 1.1 KV) 1X25 SQMM	KM	18%	26409.87
75	0501020421	CABLE(XLPE 1.1 KV) 1X50 SQMM	KM	18%	45754.33
76	0501020521	CABLE(XLPE 1.1 KV) 1X95 SQMM	KM	18%	75406.82
77	0501020621	CABLE(XLPE 1.1 KV) 1X120 SQMM	KM	18%	93837.30
78	0501020721	CABLE(XLPE 1.1 KV) 1X185 SQMM	KM	18%	153158.19
79	0501020821	CABLE(XLPE 1.1 KV) 1X240 SQMM	KM	18%	190583.36
80	0501021121	CABLE(XLPE 1.1 KV) 1CX630 SQMM	KM	18%	510524.02
81	0501022021	CABLE(XLPE 1.1 KV) 4CX6 SQMM	KM	18%	70408.08
82	0501022121	CABLE (XLPE 1.1 KV) 4CX10 SQMM	KM	18%	72989.73
83	0501022221	CABLE (XLPE 1.1 KV) 4CX25 SQMM	KM	18%	135781.37
84	0501022321	CABLE (XLPE 1.1 KV) 4CX50 SQMM	KM	18%	212857.26
85	0501022421	CABLE (XLPE 1.1 KV) 4CX120 SQMM	KM	18%	459466.03
86	0501022:121	CABLE (XLPE 1.1 KV) 4CX185 SQMM	KM	18%	686095.25
87	0501022621	CABLE (XLPE 1.1 KV) 4CX300 SQMM	KM	18%	1051107.51

11 KV GRADE XLPE CABLE

88	0501023621	CABLE(XLPE 11 KV) 1CX1000 SQMM	KM	18%	1176656.38
89	0501023821	CABLE(XLPE 11 KV) 3CX95 SQMM	KM	18%	729550.74
90	0501023921	CABLE(XLPE 11 KV) 3CX185 SQMM	KM	18%	943794.64
91	0501024121	CABLE(XLPE 11 KV) 3CX300 SQMM	KM	18%	1277704.56
92	0501024221	CABLE(XLPE 11 KV) 3CX400 SQMM	KM	18%	1785916.54

33 KV GRADE XLPE CABLE

93	0501024521	CABLE(XLPE 33 KV) 1X300 SQMM	KM	18%	603950.72
94	0501024621	CABLE(XLPE 33 KV) 1CX400 SQMM	NO	18%	763284.61
95	0501025421	CABLE(XLPE 33 KV) 1X1000 SQMM	KM	18%	1513557.05

MATERIAL COST DATA (2021-22)

SL	MAT_CODE	DESCRIPTION OF MATERIALS	UNIT	GST	COST (IN RS)
96	0501024921	CABLE(XLPE 33 KV) 3CX185 SQMM	KM	18%	1939007.39
97	0501025121	CABLE(XLPE 33 KV) 3X300 SQMM	KM	18%	2039007.39
98	0501025221	CABLE(XLPE 33 KV) 3X400 SQMM	KM	18%	2139007.39
1.1 KV GRADE AERIAL BUNCHED CABLE					
99	0501030321	CABLE(LT AERIAL BUNCHED 1.1 KV) 3CX50+1CX35 SQMM	KM	18%	160930.91
100	0501030421	CABLE(LT AERIAL BUNCHED 1.1 KV) 3CX50+1CX16+1CX35 SQMM	KM	18%	176481.44
101	0501030521	CABLE(LT AERIAL BUNCHED 1.1 KV) 3CX70+1CX16+1CX50 SQMM	KM	18%	215174.13
11 KV GRADE AERIAL BUNCHED CABLE					
102	0501031121	CABLE(HT AERIAL BUNCHED 11 KV) 3CX95+1CX70 SQMM	KM	18%	826924.19
COPPER CONTROL CABLE (1.1 KV GRADE)					
103	0501041121	CABLE(COPPER CONTROL 1.1 KV) 12CX2.5 SQMM	KM	18%	262842.08
104	0501041021	CABLE(COPPER CONTROL 1.1 KV) 8CX2.5 SQMM	KM	18%	182529.23
105	0501040721	CABLE(COPPER CONTROL 1.1 KV) 4CX2.5 SQMM	KM	18%	104805.29
DISTRIBUTION TRANSFORMER					
106	0301010541	DTR 10KVA 11/0.433KV	NO	18%	33410.20
107	0301011041	DTR 16KVA 11/0.433KV	NO	18%	50906.51
108	0301018141	DTR 25KVA 11/0.433KV (USE THIS MATERIAL CODE TO TRACK DTR SERIAL NUMBER IN THE SYSTEM)	NO	18%	63464.48
109	0301018241	DTR 63KVA 11/0.433KV (USE THIS MATERIAL CODE TO TRACK DTR SERIAL NUMBER IN THE SYSTEM)	NO	18%	107589.53
110	0301018341	DTR 100 KVA 11/0.433KV	NO	18%	144370.09
111	0301018741	DTR 160KVA 11/0.433KV	NO	18%	205888.02
112		DTR 250 KVA 11/0.433KV -OUTDOOR TYPE		18%	629697.35
113	0301019041	DTR 315 KVA 11/0.433KV -INDOOR TYPE (USE THIS MATERIAL CODE TO TRACK DTR SERIAL NUMBER IN THE SYSTEM)	NO	18%	739068.86
114	0301019141	DTR 315 KVA 11/0.433KV -OUTDOOR TYPE	NO	18%	688106.70
115	0301017841	DTR 630KVA 11/0.415KV-INDOOR & DRY TYPE	NO	18%	1925435.07
116	0301017741	DTR 630KVA 11/0.415KV-OUTDOOR & DRY TYPE	NO	18%	1925435.07
117	0301019341	DTR 630KVA 11/0.415KV-OUTDOOR & OIL COOLING TYPE	NOS	18%	1182789.36
118	0301017041	DTR 800 KVA 11/0.415KV (I/D)	NO	18%	1254940.32
119	301017241	DTR 1000 KVA 11/0 415KV (I/D)	NO	18%	1313085.68
33KV POWER TRANSFORMER					
120	0301020941	3.15 MVA 33/11KV POWER TRANSFORMER	NO	18%	4513755.98
121	0301021241	6.3 MVA 33/11KV POWER TRANSFORMER	NO	18%	6871714.13
122	0301022041	RTCC PANEL FOR 6.3 MVA TRANSFORMAR	NO	18%	87614.03
123	0301021541	10 MVA 33/11KV POWER TRANSFORMER	NO	18%	8824467.96
124	0301022141	RTCC PANEL FOR 10 MVA TRANSFORMAR	NO	18%	87614.03
33KV STATION SERVICE TRANSFORMER					
125	0301013141	100 KVA 33/0.415 KV STATION SERVICE TRANSFORMER	NO	18%	396801.07
TRANSFORMER OIL					
126	0908010252	TRANSFORMER OIL (EHV GRADE)	Kl	18%	89982.57

MATERIAL COST DATA (2021-22)

SL	MAT_CODE	DESCRIPTION OF MATERIALS	UNIT	GST	COST (IN RS)
BATTERY CHARGER					
127	0901031741	30V, 35A, AUTO & MANUAL, FLOAT-CUM-BOOST, THYRISTOR CONTROLLED BATTERY CHARGER	SET	18%	113898.24
BATTERY					
128	0901021132	30V 100 AH PLANTE TYPE LEAD ACID BATTERY	SET	18%	137806.47
129	0901040332	STANDERD ACCESSORIES Of 30V 100 AH PLANTE TYPE BATTERY BATTERY	SET	18%	14946.96
POTENTIAL TRANSFORMER, 33KV					
130	0301032241	33 KV PT (1 PHASE): OD TYPE : RATIO : 33/V3/0.11/V3 KV	NO	18%	25554.10
33KV OUTDOOR CURRENT TRANSFORMER FOR FEEDER CONTROL					
131	0301051641	33 KV CT (1 PHASE): OD TYPE : DUAL CORE CT RATIO 400-200/1-1 A	NO	18%	29934.80
33KV OUTDOOR CURRENT TRANSFORMER FOR POWER TRANSFORMER CONTROL					
132	0301054741	33 KV CT (1 PHASE): OD TYPE : DUAL CORE CT RATIO 200-100/1-1-1A	NO	18%	40959.56
33KV OUTDOOR CURRENT TRANSFORMER FOR BULK CONNECTION					
133	0301055941	33 KV CT (1 PHASE): OD TYPE : DUAL CORE CT RATIO 100-50/5-5A	NO	18%	26071.24
133(A)	0301055641	33 KV CT (1 PHASE): OD TYPE : DUAL CORE CT RATIO 100-50/1-1A	NO	18%	25989.78
LT CURRENT TRANSFORMER					
134	0301064441	LT CURRENT TRANSFORMER RING TYPE RATIO -200/5 AMPS	NO	18%	535.91
135	0301065141	LT CURRENT TRANSFORMER RING TYPE (TAPE WOUND), RATIO 400/5 AMPS. ACCURACY CLASS 0.5S	NOS	18%	547.59
11KV COMBINED CT-PT FOR BOUNDARY METERING					
136	0301070541	11 KV COMBINED CT & PT WITH CT RATIO 200-100/1A, PT 11000/110V	NO	18%	41765.16
137	0301070641	11 KV COMBINED CT & PT WITH CT RATIO 200-100/5A, PT 11000/110V	NOS	18%	42571.45
138	0301070741	11 KV COMBINED CT & PT WITH CT RATIO 300-150/1A, PT 11000/110V	NO	18%	49839.75
139	0301070841	11 KV COMBINED CT & PT WITH CT RATIO 300-150/5A, PT 11000/110V	NOS	18%	50839.75
DTR METERING CT					
140	0301065641	RESIN CAST LTCT WITH CT RATIO 200/5 FOR DTR METER	NOS	18%	408.87
141	0301065741	RESIN CAST LTCT WITH CT RATIO 600/5 FOR DTR METER	NOS	18%	474.58
SWITCHGEAR (VCB), 33 KV					
142	0302030341	36 KV VCB : 750 MVA 1000/1250 AMPS : O/D- TYPE, 30V DC	NO	18%	280656.94
143	0302031232	33KV INDOOR COMPOSITE 8 PANEL WITH VCB (2+2+2+1+1)	NOS	18%	6410686.41
144	0302031332	33KV INDOOR COMPOSITE 10 PANEL WITH VCB (2+3+1+2+1+1)	NOS	18%	7410686.41
33 KV CONTROL & RELAY (C&R) PANEL FOR TRANSFORMER CONTROL					
145	0305011041	33 KV C&R PANEL FOR GROUP CONTROL OF POWER TRANSFORMER WITHOUT COMMON EQUIPMENT	NO	18%	160573.45
146	0305011141	33 KV C&R PANEL FOR GROUP CONTROL OF POWER TRANSFORMER WITH COMMON EQUIPMENT	NO	18%	166899.26
147	0305014241	33 KV C&R PANEL FOR INDIVIDUAL CONTROL OF POWER TRANSFORMER WITHOUT DIFFERENCIAL RELAY	NO	18%	317488.78

SL	MAT_CODE	DESCRIPTION OF MATERIALS	UNIT	GST	COST (IN RS)
148	0305015241	33 KV C&R PANEL WITH DIFFERENTIAL RELAY SCADA COMPATIBLE FOR INDIVIDUAL TRANSFORMER	NOS	18%	328834.43
33 KV CONTROL & RELAY (C&R) PANEL FOR FEEDER CONTROL					
149	0305014041	33 KV C&R PANEL FEEDER CONTROL PANEL WITH NON-DIRECTIONAL RELAY	NO	18%	177259.75
150	0305015141	33 KV C&R PANEL WITH DIRECTIONAL RELAY, SCADA COMPATIBLE FOR FEEDER CONTROL	NOS	18%	207259.75
151	0305010541	33 KV C&R PANEL FEEDER CONTROL PANEL W/O CE	NO	18%	130525.83
11 KV SERIES TRIP METERING SWITCH GEAR FOR BULK CONNECTION					
152	0303050441	12 KV 350MVA,400A SERIES TRIP METERING SWG COMPLETE WITH CTR-100-50/5-5A, PTR 11000/110V	NO	18%	259748.37
153	0303050341	12 KV 350MVA,400A SERIES TRIP SWG COMPLETE WITH CTR-50-25/5-5A, PTR 11000/110V	NO	18%	250591.02
11 KV INDOOR RING MAIN UNIT (RMU) METERING SWITCH GEAR FOR BULK CONNECTION					
154	0303060432	12 KV 350MVA RMU METERING SWG CT RATIO 100-50/5-5A, PTR 11000/110V	SET	18%	635931.81
155	0303060332	12 KV 350MVA RMU METERING SWG CT RATIO 50-25/5-5A, PTR 11000/110V	SET	18%	634471.58
SHUNT TRIP SWITCHGEAR (VCB, SCADA COMP.), 11 KV(IN COMING + BUS CUUPLER + OUT GOING)					
156	0303044132	SWITCHGEAR(SHUNT TRIP) WITH VCB (12 KV 350MVA 1250/800A) 15 PNL (4+3+8)	SET	18%	5662098.00
157	0303036032	SWITCHGEAR(SHUNT TRIP) WITH VCB (12 KV 350MVA 1250/800A) 14 PNL (4+3+7)	SET	18%	5312098.00
158	0303035732	SWITCHGEAR(SHUNT TRIP) WITH VCB (12 KV 350MVA 1250/800A) 14 PNL (3+3+8)	SET	18%	5262098.00
159	0303043832	SWITCHGEAR(SHUNT TRIP) WITH VCB (12 KV 350MVA 1250/800A) 14 PNL (3+2+9)	SET	18%	5212098.00
160	0303035432	SWITCHGEAR(SHUNT TRIP) WITH VCB (12 KV 350MVA 1250/800A) 13 PNL (4+3+6)	SET	18%	4862098.00
161	0303043532	SWITCHGEAR(SHUNT TRIP) WITH VCB (12 KV 350MVA 1250/800A) 11 PNL (3+2+6)	SET	18%	4162098.00
162	0303035132	SWITCHGEAR(SHUNT TRIP) WITH VCB (12 KV 350MVA 1250/800A) 11 PNL (2+1+8)	SET	18%	4112098.00
163	0303034832	SWITCHGEAR(SHUNTTRIP) WITH VCB (12 KV 350MVA 1250/8O0A) 10 PNL (3+2+5)	SET	18%	3762098.00
164	0303034532	SWITCHGEAR(SHUNT TRIP) WITH VCB (12 KV 350MVA 1250/800A) 10 PNL (2+2+6)	SET	18%	3712098.00
165	0303034232	SWITCHGEAR(SHUNT TRIP) WITH VCB (12 KV 350MVA 1250/800A) 10 PNL (2+1+7)	SET	18%	3662098.00
166	0303036532	SWITCHGEAR(SHUNT TRIP) WITH VCB (12 KV 350MVA 1250/8O0A) 9 PNL (3+2+4)	SET	18%	3302098.19
167	0303033932	SWITCHGEAR(SHUNT TRIP) WITH VCB (12 KV 350MVA 1250/800A) 9 PNL (2+1+6)	SET	18%	3281656.38
168	0303033632	SWITCHGEAR(SHUNT TRIP) WITH VCB (12 KV 350MVA 1250/800A) 8 PNL (2+2+4)	SET	18%	2931656.38
169	0303042332	SWITCHGEAR(SHUNT TRIP) WITH VCB (12 KV 350MVA 1250/800A) 8 PNL (2+1+5)	SET	18%	2881656.38
170	0303036632	SWITCHGEAR(SHUNT TRIP) WITH VCB (12 KV 350MVA 1250/800A) 7 PNL (2+1+4)	SET	18%	2566617.87
171	0303036732	SWITCHGEAR(SHUNT TRIP) WITH VCB (12 KV 350M M 1250/8O0A) 5 PNL (2+1+2)	SET	18%	2155249.63

MATERIAL COST DATA (2021-22)

SL	MAT_CODE	DESCRIPTION OF MATERIALS	UNIT	GST	COST (IN RS)
172	0303037132	SWITCHGEAR(SHUNT TRIP) WITH VCB (12 KV 350MVA 1250/800A) 4 PNL (1+1+2)	SET	18%	1450518.84
173	0303032732	SWITCHGEAR(SHUNT TRIP) WITH VCB (12 KV 350MVA 1250/800A) 4 PNL (1+0+3)	SET	18%	1390518.84
174	0303036832	SWITCHGEAR(SHUNT TRIP) WITH VCB (12 KV 350MVA 1250/800A) 3 PNL (1+1+1)	SET	18%	1092999.59
175	0303041432	SWITCHGEAR(SHUNT TRIP) WITH VCB (12 KV 350MVA 1250/800A) 3 PNL (1+0+2)	SET	18%	992999.59
176	0303032432	SWITCHGEARISHUNT TRIP) WITH VCB (12 KV 350MVA 1250/800A) 3 PNL (0+0+3)	SET	18%	853026.46
177	0303041132	SWITCHGEARISHUNT TRIP) WITH VCB (12 KV 350MVA 1250/800A) 2 PNL (1+0+1)	SET	18%	753026.46
178	0303037232	12 KV SCADA COMPATIBLE SHUNT TRIP SWITCHGEAR PANEL WITH VCB 2 PANEL (1+1+0)	SET	18%	735480.33
179	0303037332	12 KV SCADA COMPATIBLE SHUNT TRIP SWITCHGEAR PANEL WITH VCB 2 PANEL (0+1+1)	SET	18%	691939.08
180	0303031532	SWITCHGEAR(SHUNT TRIP) WITH VCB (12 KV 350MVA 1250/800A) 2 PNL(0+0+2)	SET	18%	685480.33
181	303036932	SWITCHGEARISHUNI TRIP) WITH VCB (12 KV 350MVA 1250/800A) 1 PNL(0+0+1) (WITH BUS BAR)	SET	18%	357519.26

11 KV OUTDOOR RING MAIN UNIT (RMU) SWITCH GEAR

182	0303062232	SCADA RMU, 11KV OUTDOOR NON EXTENSIBLE 4-WAY (2 LBS+2 OG) FOR OIL COOLED 315KVA DTR	SET	18%	667908.47
183	0303062332	SCADA RMU, 11KV OUTDOOR NON-EXTENSIBLE 4-WAY (2 LBS+2 OG) FOR OIL COOLED 630KVA DTR	SET	18%	707879.27

1PH & 3PH WHOLE CURRENT STATIC ENERGY METER

184	0401010741	SINGLE PHASE 2W STATIC METER (5-30)A WITH P.P. BOX	NO	18%	1044.44
185	0401010641	SINGLE PHASE 2W STATIC METER (5-30)A WITHOUT P.P. BOX (USE THIS MATERIAL CODE TO TRACK DTR SERIAL NUMBER IN THE SYSTEM)	NOS	18%	956.57
186	0401021541	THREE PHASE 4W (5-30)A, DIMS, WHOLE CURRENT STATIC METER (USE THIS MATERIAL CODE TO TRACK DTR SERIAL NUMBER IN THE SYSTEM)	NOS	18%	6467.10
187	0401021441	THREE PHASE 4W STATIC METER (10-60)A WITH PP BOX & LPR	NO	18%	6620.56
188	0912011941	LPR MODULE WITH MRI & ACCESSORIES FOR 3X(10-60)A ENERGY METER	NOS	18%	93315.10
189	0401021741	THREE PHASE 4W STATIC METER (20-100)A	NO	18%	7596.14

1PH & 3PH PREPAID ENERGY METER

190	0401010541	PREPAID 1PH AC STAT. MTR. (5-30A) WH PP BOX	NO	18%	7410.32
191	0401010841	1PH AC STAT. MTR. (10-60A) PRE-PAID WH SL NO (USE THIS MATERIAL CODE TO TRACK DTR SERIAL NUMBER IN THE SYSTEM)	NO	18%	8056.64
192	0401021641	3PH 4W AC STAT. MTR. (20-80A) PRE-PAID WH SL NO (USE THIS MATERIAL CODE TO TRACK METER SERIAL NUMBER IN THE SYSTEM)	NO	18%	16303.88

1PH & 3PH IMPORT EXPORT ENERGY METER WHOLE CURRENT

193		1PH 2W 5-30A EXPORT/IMPORT MTR WH SL NO (USE THIS MATERIAL CODE TO TRACK DTR SERIAL NUMBER IN THE SYSTEM)		18%	2190.36
194	0401021241	THREE PHASE STATIC METER (5-30)A IMPORT EXPORT TYPE	NO	18%	6106.99

SL	MAT_CODE	DESCRIPTION OF MATERIALS	UNIT	GST	COST (IN RS)
195	0401021341	THREE PHASE STATIC METER (20-100)A IMPORT-EXPORT TYPE (USE THIS MATERIAL CODE TO TRACK DTR SERIAL NUMBER IN THE SYSTEM)	NO	18%	6730.69
3PH IMPORT EXPORT ENERGY METER - CT OPERATED					
196	0401034441	3P 4W LTCT EXPORT IMPORT BLK MTR WH SL NO	NOS	18%	6720.42
197	0401034541	3P4W 11KV EXPORT IMPORT BLK MTR WH SL NO (USE THIS MATERIAL CODE TO TRACK DTR SERIAL NUMBER IN THE SYSTEM)	NOS	18%	9598.76
198	0401034641	3P4W 33KV EXPORT IMPORT BLK MTR WH SL NO (USE THIS MATERIAL CODE TO TRACK DTR SERIAL NUMBER IN THE SYSTEM)	NOS	18%	9598.76
LT CT OPERATED TOD ENERGY METER					
199	0401034041	3PH 4 W LT TOD METER CT RATIO 200/5 A FOR LT BULK	NO	18%	6496.80
CT & PT OPERATED 11KV ENERGY METER					
200	0401033341	3 PH 3 W NONDLMS METER WITH CTR 50/5 A FOR 11 KV BULK (USE THIS MATERIAL CODE TO TRACK DTR SERIAL NUMBER IN THE SYSTEM)	NOS	18%	9306.07
201	0401034141	3PH 4W DLMS WITH CT RATIO 50/5 A FOR 11KV BULK (USE THIS MATERIAL CODE TO TRACK DTR SERIAL NUMBER IN THE SYSTEM)	NO	18%	9308.63
CT & PT OPERATED 33KV ENERGY METER					
202	0401030741	3 PH 4W CT RATIO 100/5A FOR 33 KV BULK CONSUMER	NO	18%	14098.90
203	0401033941	3PH 4W CT/PT OPERATED CT RATIO 100/1A, FOR 33 KV BULK	NO	18%	9306.07
CT & PT OPERATED 132KV ENERGY METER					
204	0401030541	3 PHASE 4WIRE STATIC 132 KV CT-PT OPERATED HT TRIVECTOR TOD FOR 132 KV BULK, 0.2S	NO	18%	42755.16
CT & PT OPERATED TRACTION ENERGY METER					
205	0401033441	1 PH 2 W STATIC 25 KV CT-PT OPERATED TRIVECTOR TOD ENERGY METER FORTRACTION APPLICATION. 0.2S	NOS	18%	37447.22
206	0401030641	1 PH 2W STATIC 132 KV CT-PT OPERATED TRIVECTOR TOD ENERGY METER FOR 132 KV TRACTION POWER, 0.2S	NO	18%	42755.16
CT & PT OPERATED FEEDER ENERGY METER					
207	0401030941	3 PH 3W CT/PT OPERATED AMR. TRIVECTOR 11KV FEEDER METER	NO	18%	13603.22
208	0401031541	3-PH 3-WIRE CT/PT OPERATED AMR, TRI-VECTOR FEEDER METER FOR 33 KV SYSTEM	NO	18%	14392.85
209	0401034241	3-PH 4-WIRE (1A) AMR.TRI-VECTOR FEEDER METER FOR 33 KV SUB-STN (USE THIS MATERIAL CODE TO TRACK DTR SERIAL NUMBER IN THE SYSTEM)	NOS	18%	9308.63
210	0401034741	MULTI-FEEDER METERING RACK WITH SUMMATION UNIT FOR TWO FEEDER SUMMATION	NOS	18%	775530.16
CT OPERATED DTR ENERGY METER					
211	0401032041	3PH 4W CT OPERATE0 FULLY STATIC AMR, TRI VECTOR VETER FOR DTR WITH PP BOX	NO	18%	11176.56
212	0401031741	METER FOR DTR UPTO 100KVA RATING WITH MODEM AND INBUILD CT	NO	18%	22776.81
213	0401031341	3PH 4 W CT OPERATED FULLY STATIC AMR, TRI-VECTOR DLMS METER FOR DTR	NOS	18%	6104.51
CT & PT OPERATED BOUNDERY ENERGY METER					
214	0401034341	3PH 4W 11KV (1A, BOUNDARY MTR WH SL NO (USE THIS MATERIAL CODE TO TRACK DTR SERIAL NUMBER IN THE SYSTEM)	NOS	18%	12842.64

MATERIAL COST DATA (2021-22)

SL	MAT_CODE	DESCRIPTION OF MATERIALS	UNIT	GST	COST (IN RS)
SEAL					
215	0902020741	POLYCARBONATE SECURITY SEAL 20CM(ORANGE COLOUR)	NO	18%	5.22
216	0902021141	POLYCARBONATE SECURITY SEAL (PATENTED) 20 CM (LIGHT GREEN COLOUR)	NO	18%	8.36
217	0902020841	POLYCARBONATE SECURITY SEAL (PATENTED) 20 CM (BARCODED YELLOW COLOUR)	NO	18%	10.62
218	0902020941	POLYCARBONATE SECURITY SEAL (PATENTED) 40CM (TRANSPERENT COLOUR)	NO	18%	9.83
CUT-OUT FUSE UNIT					
219	0504122141	RE-WIRABLE PORCELAIN CUT OUT FUSE UNIT 16 AMP	NOS	18%	82.51
220	0504122241	RE-WIRABLE PORCELAIN CUT OUT FUSE UNIT 32 AMP	NOS	18%	134.07
221	0504122341	RE-WIRABLE PORCELAIN CUT OUT FUSE UNIT 63 AMP	NOS	18%	291.37
222	0504122441	RE-WIRABLE PORCELAIN CUT OUT FUSE UNIT 100 AMP	NOS	18%	478.90
223	0504122541	RE-WIRABLE PORCELAIN CUT OUT FUSE UNIT 200 AMP	NOS	18%	1011.13
224	0504122641	RE-WIRABLE PORCELAIN CUT OUT FUSE UNIT 300 AMP	NOS	18%	1724.45
225	0504122/41	RE-WIRABLE PORCELAIN CUT OUT FUSE UNIT 400 AMP	NOS	18%	2515.24
226	0504122841	RE-WIRABLE PORCELAIN CUT OUT FUSE UNIT 500 AMP	NOS	18%	3054.19

LOCAL PURCHASE ITEM FOR ESTIMATION PURPOSE 2021-22

SL	MAT_CODE	DESCRIPTION OF MATERIALS	UNIT	GST	COST (IN RS)
M.S. 'V' BRACKET 11 KV					
1	0113020641	11KV "V" BRACKET FOR PCC POLE 8M LONG	NOS	18%	961.42
2	0113020741	11KV "V" BRACKET FOR PCC POLE 9M LONG	NOS	18%	1084.77
3	0113020841	11 KV "V" BRACKET FOR RAIL POLE	NOS	18%	953.92
M.S. 'V' BRACKET 33 KV					
4	0113020941	33KV "V" BRACKET FOR PCC POLE 9M LONG	NOS	18%	1696.51
5	0113021141	33 KV "V" BRACKET FOR RAIL POLE	NOS	18%	1721.03
M.S. TOP ADAPTOR 11 KV					
6	0113021241	11 KV TOP ADAPTOR FOR PCC POLE 8M LONG	NOS	18%	361.08
7	0113021341	11 KV TOP ADAPTOR FOR PCC POLE 9M LONG	NOS	18%	417.26
8	0113021441	11 KV TOP ADAPTOR FOR RAIL POLE	NOS	18%	356.57
M.S. TOP ADAPTOR 33 KV					
9	0113021541	33 KV TOP ADAPTOR FOR PCC POLE 9M LONG	NOS	18%	1178.71
10	0113021641	33 KV TOP ADAPTOR FOR RAIL POLE	NOS	18%	737.06
L.T. KIOSK FOR BULK METERING					
11	0407010241	LT MTR KIOSK 415V STLSHT COVR	NOS	18%	12696.16
LT DISTTBUTTON BOX FOR DTR					
12	0407010541	LT DISTRIBUTION KIOSK FOR 100 KVA TRNF	NOS	18%	8733.09
13	0407010641	LT DISTRIBUTION KIOSK FOR 25 KVA TRNF	NOS	18%	8733.09
14	0407010741	LT DISTRIBUTION KIOSK FOR 63 KVA TRNF	NOS	18%	8733.09
15	0407010841	LT DISTRIBUTION KIOSK FOR 315 KVA TRNF	NOS	18%	19999.00
G.I. TURN BUCKLE					
16	0912011441	TURN BUCKLE 18X5/8"	NOS	18%	182.36
17	0912013341	TURN BUCKLE 18x3/4"	NOS	18%	211.22
PG CLAMP					

MATERIAL COST DATA (2021-22)

SL	MAT_CODE	DESCRIPTION OF MATERIALS	UNIT	GST	COST (IN RS)
18	0505011141	PG CLAMP FOR A.C.S.R.DOG	NOS	18%	328.69
19	0505010641	PG CLMP-WSL/RBT (30/50 SQMM)	NOS	18%	131.45
D IRON CLAMP					
20	0505031541	D IRON CLAMP 1" x 3.5"	NOS	18%	33.02
POLE CLAMP					
21	0505031641	UPPER CLAMP - L.T.BKT.S0X6 FLAT(PCC POLE)	NOS	18%	96.90
22	0505031741	LOWER CLAMP - l.T.BKt S0X6 FLAT(PCC PO .£)	NOS	18%	97.72
23	0505034941	CLAMP FOR 8M PCC POLE	NOS	18%	170.01
24	0505035041	CLAMP FOR 9M PCC POLE	NOS	18%	174.45
25	0505035141	CLAMP FOR 8M PCC POLE(BOT)	NOS	18%	187.35
26	0505035241	CLAMP FOR 9M PCC POLE(BOT)	NOS	18%	201.68
SHACKLE STRAP WITH NUT & BOLTS					
27	0506010331	SHACKLE STRAP BIG 185X30X3	PAA	18%	34.35
28	0506010531	GI SHACKLE STRAP 9" WITH NUT & BOLT	PAA	18%	46.76
ALUMINIUM BINDING WIRE					
29	0503020312	AL. BINDING WIRE 5MM/6SWG	KG	18%	381.03
30	0903013212	AL BINDING TAPE - 1/4"	KG	18%	478.99
PLASTIC TAPE/ROLL					
31	0903013545	PLASTIC TAPE - NON ADHESIVE - 1"	ROL	18%	26.29
C.I. REEL					
32	0508040641	CI REEL INSULATOR	NOS	18%	31.05
SHACKLE INSULATOR					
33	0508040341	PORCELAIN SHACKLE INSULATOR 2" X 21/2"	NOS	18%	16.93
34	0508040441	PORCELAIN SHACKLE INSULATOR 3" x 31/2"	NOS	18%	19.41
GUY INSULATOR					
35	0508040841	PORCELAIN GUY INSULATOR HT	NOS	18%	47.38
36	0508040741	PORCELAIN GUY INSULATOR LT	NOS	18%	18.37
LT SPACERS					
37	0504070341	LT SPACER - 1 PHASE 2 WIRE	NOS	18%	27.06
38	0504070641	LT SPACER - 2 PHASE 3 WIRE	NOS	18%	40.89
39	0504070441	LT SPACER - 3 PHASE 4 WIRE	NOS	18%	60.11
40	0504070541	LT SPACER - 3 PHASE S WIRE	NOS	18%	71.35
XLPE CABLE JOINING KIT, 11KV INDOOR TYPE					
41	0504042641	11KV I/D HS Ter.Jnt. FOR 3x95 SQMM XLPE CAB	NOS	18%	5031.53
42	0504043241	11KV I/D HS Ter.Jnt. FOR 3x185 SQMM XLPE CAB	NOS	18%	5258.12
43	0504043841	11KV I/D HS Ter.Jnt. FOR 3x300 SQMM XLPE CAB	NOS	18%	6431.34
XLPE CABLE JOINING KIT, 11KV OUTDOOR TYPE					
44	0504042541	11KV O/D HS Ter.Jnt. FOR 3x95 SQMM XLPE CAB	NOS	18%	7421.56
45	0504043141	11KV O/D HS Ter.Jnt. FOR 3x185 SQMM XLPE CAB	NOS	18%	8186.43
46	0504043741	11KV O/D HS Ter.Jnt. FOR 3x300 SQMM XLPE CAB	NOS	18%	9294.55

MATERIAL COST DATA (2021-22)

SL	MAT_CODE	DESCRIPTION OF MATERIALS	UNIT	GST	COST (IN RS)
XLPE CABLE JOINING KIT, 11KV STRAIGHT THROUGH TYPE					
47	0504042741	11KV ST. THR. HS JNT. FOR 3x95 SQMM XLPE CAB	NOS	18%	13449.80
48	0504057941	11KV ST. THR. HS JNT. FOR 3x185 SQMM XLPE CAB	NOS	18%	15651.52
49	0504043941	11KV ST. THR. HS JNT. FOR 3x300 SQMM XLPE CAB	NOS	18%	17957.58
50	0504047341	11KV ST. THR. HS JNT. FOR 3x400 SQMM XLPE CAB	NOS	18%	18103.56
XLPE CABLE JOINING KIT, 33KV INDOOR TYPE					
51	0504045041	33KV I/D HS Ter.Jnt. FOR 3x185 SQMM XLPE CAB	NOS	18%	17099.22
52	0504045641	33KV I/D HS Ter.Jnt. FOR 3x300 SQMM XLPE CAB	NOS	18%	18155.46
53	0504045941	33KV I/D HS Ter.Jnt. FOR 3x400 SQMM XLPE CAB	NOS	18%	19392.95
54	0504049741	33KV I/D HS Ter.Jnt. FOR 1x1000 SQMM XLPE CAB	NOS	18%	7096.74
XLPE CABLE JOINING KIT, 33KV OUTDOOR TYPE					
55	0504044941	33KV O/D HS Ter.Jnt. FOR 3x185 SQMM XLPE CAB	NOS	18%	19139.45
56	0504045541	33KV O/D HS Ter.Jnt. FOR 3x300 SQMM XLPE CAB	NOS	18%	24604.72
57	0504045841	33KV O/D HS Ter.Jnt. FOR 3x400 SQMM XLPE CAB	NOS	18%	26532.72
58	0504049541	33KV O/D HS Ter.Jnt. FOR 1x1000 SQMM XLPE TAB	NOS	18%	8761.41
XLPE CABLE J0ININ6 KIT, 33KV STRAIGHT THROUGH TYPE					
59	0504045141	33KV ST. THR. HS JNT. FOR 3x185 SQMM XLPE CAB	NOS	18%	40255.18
60	0504045741	33KV ST. THR. HS JNT. FOR 3x300 SQMM XLPE CAB	NOS	18%	41533.12
61	0504046041	33KV ST. THR. HS JNT. FOR 3x400 SQMM XLPE CAB	NOS	18%	46325.41
62	0504049641	33KV ST. THR. HS JNT. FOR 1x1000 SQMM XLPE CAB	NOS	18%	18252.93
1.1 KV STRAIGHT THROUGH TYPE JOINING KIT					
63	0504054141	1.1KV ST. THR. JNT. FOR (4/3.5x50 SQMM)	NOS	18%	1760.42
64	0504054341	1.1KV ST. THR. JNT. FOR (4/3.5x95 SQMM)	NOS	18%	1964.64
65	0504054441	1.1KV ST. THR. JNT. FOR (4/3.5x120 SQMM)	NOS	18%	2468.22
66	0504054541	1.1KV ST. THR. JNT. FOR (4/3.5x185 SQMM)	NOS	18%	3077.79
67	0504054641	1.1KV ST. THR. JNT. FOR (4/3.5x240 SQMM)	NOS	18%	4307.69
68	0504054741	1.1KV ST. THR. JNT. FOR (4/3.5x300 SQMM)	NOS	18%	4370.58
69	0504054841	1.1KV ST. THR. JNT. FOR (4/3.5x400 SQMM)	NOS	18%	6980.76
1.1 KV 'T' JOINING KIT					
70	0504055141	1.1KV TEE JNT. FOR (4/3.5x50-25/16 SQMM)	NOS	18%	4472.80
71	0504055241	1.1KV TEE JNT. FOR (4/3.5x70-25/16 SQMM)	NOS	18%	6709.20
72	0504055341	1.1KV TEE JNT. FOR (4/3.5x95-25/16 SQMM)	NOS	18%	7348.17
HT ARIAL BUNCHED CABLE ACCESSORIES					
73	0504023041	PAD-CON. FOR 11KV(1X95 SMM) ABC	NOS	18%	486.77
74	0504022941	WEDGE-CON. FOR 11KV(1X95 SQMM) ABC	NOS	18%	524.23
75	0504053341	11KV I/D HS Ter.Jt. FOR (1x95 SQMM)ABC	NOS	18%	1865.94
76	0504053241	11KV O/D HS Ter.Jt. FOR (1x95 SQMM)ABC	NOS	18%	2007.58
77	0504053441	11KV ST. THR. HS Jt. FOR (1x95 SQMM)ABC	NOS	18%	4523.18
78	0504038541	TEE JNT TAP OFF 11KV ABC TO DTR-1X95 SQMM	NOS	18%	5214.50
LT ARIAL BUNCHED CABLE ACCESSORIES					
79	0504026841	INSULATION-PIERCING CONNECTOR (ABC) - 16SQ MM	NOS	18%	88.93
80	0504030341	PIERCING INSULATION STRAIGHT THROUGH JOINT (ABC)-16SQMM	NOS	18%	126.30
81	0504026941	INSULATION-PIERCING CONNECTOR (ABC) 35-50 SQMM	NOS	18%	95.09

MATERIAL COST DATA (2021-22)

SL	MAT_CODE	DESCRIPTION OF MATERIALS	UNIT	GST	COST (IN RS)
82	0504030741	PIERCING INSULATION STRAIGHT THROUGH JOINT (ABC) -35 SQMM N.WIRE	NOS	18%	130.89
83	0504026741	INSULATION-PIERCING CONNECTOR (ABC) 50-70 SQMM	NOS	18%	106.35
84	0504030841	PIERCING INSULATION STRAIGHT THROUGH JOINT (ABC) -50 SQMM N.WIRE	NOS	18%	164.57
85	0504030941	PIERCING INSULATION STRAIGHT THROUGH JOINT (ABC) -50 SQMM POWER CABLE	NOS	18%	164.57
86	0504031141	PIERCING INSULATION STRAIGHT THROUGH JOINT (ABC) -70 SQMM POWER CABLE	NOS	18%	182.53
87	0504027041	INSULATION-PIERCING CONNECTOR (ABC) -95 SQMM	NOS	18%	108.00
88	0504027141	INSULATION-PIERCING CONNECTOR - ABC TO ABC TEE JOINT	NOS	18%	170.49
89	0504031241	PIERCING INSULATION STRAIGHT THROUGH JOINT (ABC) -CABLE END CAP	S	18%	20.31
90	0504027441	BI-METALUC CRIMPING TYPE WATER PROOF LUG-16 SQMM ST LT(ABC)	NOS	18%	167.19
91	0504027541	BI-METALLIC CRIMPING TYPE WATER PROOF LUG-35 SQMM MSNGR(ABC)	NOS	18%	221.64
92	0504027741	BI-METALLIC CRIMPING TYPE WATER PROOF LUG-50 SQMM PWI'(ABC)	NOS	18%	229.06
93	0504027641	BIMETALLIC CRIMPING TYPE WATER PROOF LUG-50 SQMM MSNGR(ABC)	NOS	18%	234.42
94	0504027841	BIMETALLIC CRIMPING TYPE WATER PROOF LUG-70 SQMM PWR(ABC)	NOS	18%	247.50
95	0504060941	LT DIST. BOX 3PH CON.WH ST. STRAP & BUCKLE-ABC	NOS	18%	1632.58
96	0504140641	CAB END CAP FOR DIFF. SIZE AB CABLE	NOS	18%	13.62
97	0504151441	CAB TIE WH ADJ. LOCKING ARRANGEMENT.	NOS	18%	6.30

CLAMP: ARIAL BUNCHED CABLE ACCESSORIES

98	0505036541	SUSP. CLAMP HT ABC 70-150 SQMM MESENGER	NOS	18%	156.62
99	0505030641	SUSPENTION CLAMP WITH BRKT 35 SQMM MESENGER	NOS	18%	352.89
100	0505030241	SUSPENTION CLAMP WITH BRKT 180 SQMM MESENGER	NOS	18%	442.60
101	0505030341	ANCHORING CLAMP 180 SQMM : MESSENGER	NOS	18%	472.19
102	0505034141	DEAD END CLAMP-LT ABC (3X70+1X16+1X50 SQMM)	NOS	18%	307.84
103	0505030841	EYE HOOK FOR ANCHOR & SUSPN. CLAMP	NOS	18%	100.67

SAFETY DEVICES

104	0201050111	G.I. BARBED WIRE	MT	18%	103258.06
105	0910010241	CAUTION BOARD - 11KV	NOS	18%	143.95
106	0910011641	CAUTION BOARD - 400V	NOS	18%	143.95
107	0910012141	CAUTION BOARD - 33KV	NOS	18%	143.95

Annexure-A : Final Price List i.r.o. Supply of Items required for Repairing of both Stack and Wound Core Type Damaged/Defective Transformers (NIT No.: P- 35/ 2017-18/ DTR/ RC/ PC-III, opened on 09/03/2018)				
Sl. No.		**Description of Items**	**Unit**	**Rate (Rs.) without GST**
1		Supply of Bushing in replacement of broken one as per IS:3347 of 1979 & IS: 2099 of 1986 and their latest amendment		
	a)	33 KV 250 Amps	Each	595.00
	b)	12 KV 250 Amps	Each	120.00
	c)	12 KV 630 Amps	Each	158.00
	d)	1.1 KV 250 Amps	Each	21.00
	e)	1.1 KV 630 Amps	Each	38.00
	f)	1.1 KV 1000 Amps	Each	67.00
2		Supply of Studs for Busing complete with Nuts, Washers and Cap Fittings according to requirement conforming to IS:3347 of 1979 & IS: 2099 of 1986 and their latest amendment		
	a.	Brass Stud with Brass Fittings complete with Nuts, Washers & Cap Fittings		
	(i)	12 KV 250 Amps	Per Kg	554.00
	(ii)	1.1 KV 250 Amps	Per Kg	554.00
	(iii)	1.1 KV 630 Amps	Per Kg	554.00
	(iv)	1.1 KV 1000 Amps	Per Kg	554.00
	b.	Aluminium Stud with Aluminium Fittings complete with Nuts, Washers etc.		
	(i)	12 KV 250 Amps	Per Kg	286.00
	(ii)	1.1 KV 250 Amps	Per Kg	288.00
	c.	Copper Stud with Copper Fittings complete with Nuts etc.		
	(i)	12 KV 250 Amps	Per Kg	690.00
	(ii)	1.1 KV 250 Amps	Per Kg	662.15
	(iii)	1.1 KV 630 Amps	Per Kg	633.36
	(iv)	1.1 KV 1000 Amps 30 mm Stud	Per Kg	656.39
	(v)	1.1 KV 1000 Amps 25 mm Stud	Per Kg	667.00
	d.	Brass Stud with Brass Fittings complete with Nuts, etc. 34KV/250 Amps	Per Kg	549.00
	e.	Copper Stud with Brass Fittings complete with Nuts etc. 34 KV/250 Amps	Per Kg	658.00
3		Oil Seal of Bushing made of Neoprene rubber		
	(i)	1.1 KV 250 Amps	Each	4.50
	(ii)	1.1 KV 630 Amps	Each	7.00
	(iii)	1.1 KV 1000 Amps	Each	13.00
	(iv)	12 KV 250 Amps	Each	5.40
	(v)	33 KV 250 Amps	Each	7.00
4		Supply of C.I./M.S. Clamp for Fixing of HT Bushing		
	a.	33 KV Busing	each	36.00
	b.	11 KV Busing	each	33.00
5		Supply of Arcing Horn assembly		
	a.	33 KV Single Gap Clamp	Per Pair	36.00
	b.	11 KV Single Gap Clamp	Per Pair	36.00
		Supply of Insulating materials for assembly		
	a.	Phase separator, Spacers, axial ducts, cylinder's core yoke insulation		
	(i)	Raman make sigma con. 3.1 pre-compressed pressphan paper board	Per Kg	320.00
	(ii)	"K" Grade Scnapatty White lay pre-compressed Press Board		

Sl. No.		Description of Items	Unit	Rate (Rs.) without GST
6		Rate per Kg. with thickness of 0.75 mm	Per Kg	246.50
		-Do - with thickness of 1.5 to 3.2 mm	Per Kg	236.50
		-Do - with thickness of 5 mm	Per Kg	224.50
	b.	Other (viz Ampere tape, Cotton Tape, Bakelite Tube and Sleeve Rings)		
	(i)	For 10 KVA to 25 KVA 11/0.433 KV 3 Ph. Each Transformers	Each	167.46
	(ii)	For 50/63 KVA Transformers	Each	196.27
	(iii)	For 100/160 KVA Transformers	Each	244.94
	(iv)	For 250 KVA Transformers	Each	353.22
	(v)	For 300/315 KVA Transformers	Each	422.54
	(vi)	For 500 KVA Transformers	Each	633.97
	(vii)	For 630 KVA Transformers	Each	792.58
	(viii)	For 100 KVA 33/0.433 KV Transformers	Each	380.00
7		Supply of Neoprene Rubberized Gasket Sheet		
	(i)	3 mm Thickness	PerSq.Mtr	585.44
	(ii)	5 mm Thickness	Per Sq.Mtr	652.32
	(iii)	6 mm Thickness	PerSq.Mtr	796.11
8		Rotary Switch with Handle		
	a.(i)	250 KVA 5 Position	Each	718.00
	(ii)	250 KVA 7 Position	Each	993.00
	b.(i)	315 KVA 5 Position	Each	759.00
	(ii)	315 KVA 7 Position	Each	1002.00
	c.(i)	500 KVA 5 Position	Each	1062.00
	(ii)	500 KVA 7 Position	Each	1249.00
	d.(i)	630 KVA 5 Position	Each	1002.00
	(ii)	500 KVA 7 Position	Each	1249.00
9		Supply of finished new E.C. Grade Copper Conductor with insulation		
	(i)	TPC	Per Kg	623.95
	(ii)	DPC	Per Kg	623.95
	(iii)	SE	Per Kg	688.71
		Loss: Max. 5% allowed		
10		Supply of finished new E.C. Grade Copper Strip DPC (50 Sq. mm) with insulation (Loss: Max. 5% allowed	Per Kg	559.21
11		Supply of finished new Aluminium Conductor Coils/Wires with insulation		
	(i) (a)	S.E. Upto 25 KVA	Per Kg	331.58
	(b)	S.E. above 25 KVA	Per Kg	331.58
	(ii)	TPC/DPC	Per Kg	311.96
		Loss: Max. 5% allowed		
12		Supply of finished new Aluminium Strip DPC/TPC	Per Kg	298.79
		Max. Loss 5% allowed		
13		Supply of M.S. Bolts & Nuts (assorted size) according to requirement (size to be mentioned as per BS 916 BSW)		
		For all ratings	Per Kg	75.68
14		Supply of Hot-Trip galvanized Nut, Bolts & Washers - Assorted size		
		For all rating	Per Kg	89.14
15		Supply of Silica gel Breather with container and first filling		
	a)	10-25 KVA 11/6.6/6/0.4 KV	Each	89.54
	b)	50/63 KVA 11/6.6/6/0.4 KV	Each	102.66
	c)	100/160 KVA 11/6.6/6/0.4 KV	Each	156.24
	d)	250 KVA 11/6.6/6/0.4 KV	Each	235.98

Sl. No.		Description of Items	Unit	Rate (Rs.) without GST
	e)	315 KVA 11/6.6/6/0.4 KV	Each	237.49
	f)	500/630 KVA 11/6.6/6/0.4 KV	Each	281.69
16		Supply of New Cooling round pipe including Welding & Fittings	Per Running Mtr.	102.74
17		Supply of Drain Valve / Filter Valve with plug in replacement of old one		
	a)	1/4"	Each	93.40
	b)	3/4"	Each	130.16
	c)	1"	Each	214.38
	d)	1 1/4"	Each	265.31
	e)	1 1/2"	Each	321.67
	f)	2"	Each	497.82
18	(i)	BASE PLATE WITH FIXING		
		(The Base Plate is to be made of M.S. Material 2.5 mm thick measuring 6"x4" to be fixed with the body of the Transformer Tank suitably by continues welding on tank body)	L.S. for Each	12.00
	. (ii)	NAME PLATE WITH FIXING: (The Name Plate is to be made of anodized Aluminum 0.6 mm thick measuring 4"x2". The Name Plate is to be fixed on the base plate by machine screws and welded. The Name Plate should indicate the following)	L.S. for Each	25.00
	a)	Name of the Repairer's Firm		
	b)	Name of the Store where from received		
	c)	Make/Serial No.		
	d)	Voltage ratio		
	e)	KVA ratings		
	f)	% Impedance at 75°C		
	g)	Load Loss at 100% Loading		
	h)	No load Loss at rated voltage & freq.		
	i)	Total Loss at 50% loading (If applicable)		
	j)	Date of test		
		(The above particulars are to be letter punched on the Name Plate. The general lettering should be attached on Aluminium Plate and anodized)		.
	iii)	DTR Indexing (As per instruction of ordering officer)		
		As per circular by The Director (Dist) Communicated vide memo no. Director (Dist)/ B-6/2(1-52) & (53-78) Dated 15.01.09	Average rate from Tr. Health Check up	28.35

Annexure-B : Final Price List i.r.o. Labour & Supervisory Items for Repairing of Damaged/Defective Stack Core Type DTR (NIT No.: P- 35/ 2017-18/ DTR/ RC/ PC-III, opened on 09/03/2018)

Sl. No.		Description of Items	Unit	Rate (Rs.) without GST
1		Joint preliminary/final Survey and preparation of report together with estimate of repair work involved (to be submitted in quadruplicate)		
	a)	10 KVA/16 KVA/25 KVA/, 11/6.6/6/0.433 KV	Each	835.70
	b)	50 KVA/63 KVA, 11/6.6/6/0.433 KV	Each	870.50
	c)	100/160 KVA, 11/6.6/6/0.433 KV	Each	1047.43
	d)	250 KVA, 11/6.6/6/0.433 KV	Each	1330.73
	e)	315 KVA, 11/6.6/6/0.433 KV	Each	1569.57
	f)	500 KV A/630 KVA, 11/6.6/6/0.433 KV	Each	1987.28
	g)	50 KVA, 33/0.433 KV	Each	870.50

Sl. No.		Description of Items	Unit	Rate (Rs.) without GST
	h)	100 KVA, 33/0.433 KV	Each	1047.43
	i)	250 KVA, 33/0.433 KV	Each	1329.12
2		Re-assembly of Transformer found condemned after inspection		
	a)	10 KVA/16 KVA/25 KVA, 11/6.6/6/0.433 KV	Each	353.89
	b)	50 KVA/63 KVA, 11/6.6/6/0.433 KV	Each	452.48
	c)	100/160 KVA, 11/6.6/6/0.433 KV	Each	566.67
	d)	250 KVA, 11/6.6/6/0.433 KV	Each	800.57
	e)	315 KVA, 11/6.6/6/0.433 KV	Each	832.50
	f)	500 KVA/630 KVA, 11/6.6/6/0.433 KV	Each	858.58
	g)	50 KVA, 33/0.433 KV	Each	568.55
	h)	100 KVA, 33/0.433 KV	Each	609.15
	i)	250 KVA, 33/0.433 KV	Each	905.02
3		Labour Charges for preparation and fittings of new Copper Coil in replacement of damaged ones by providing inter-layer insulation (Inter layer insulation material is to be used as per recommendation of manufacturer of Insulating material)		
	(A)	11/6.6/6 KV Coils		
	i)	HV Coils Insulation TPC	Per Kg	72.17
	ii)	HV Coils Insulation DPC	Per Kg	64.83
	iii)	HV Coils Insulation SE	Per Kg	77.30
	(B)	33 KV Coils		
	i)	HV Coils Insulation TPC	Per Kg	63.14
	ii)	HV Coils Insulation DPC	Per Kg	74.10
	iii)	HV Coils Insulation SE	Per Kg	79.00
	(C)	400 Volts Coils		
	i)	LV Coil Insulation DPC (Round)	Per Kg	56.00
	ii)	LV Coil Insulation DPC (Rectangular)	Per Kg	58.50
4	(A)	Labour Charges for rewinding with re-insulation of existing Copper Conductor with replacement of inter-layer insulation (Inter layer insulation material is to be used as per recommendation of manufacturer of Insulating material)		
	i)	33KVCoil:TPC/DPC	Per Kg	72.17
	ii)	11 KV 6.6 KV Coil: DPC/TPC	Per Kg	72.17
	(B)	Labour Charges for rewinding without re-insulation of existing Copper Conductor		
	i)	33KVCoil:TPC/DPC	Per Kg	72.17
	ii)	11 KV 6.6 KV Coil :DPC/TPC	Per Kg	70.88
5		Labour Charges for rewinding with re-insulation with inter-layer insulation of old LV (400/415/433 Volts) Copper Coil with ducting (Inter layer insulation material is to be used as per recommendation of manufacturer of Insulating material)		
	a)	LV Coils Insulation DPC (Round)	Per Kg	80.27
	b)	LV Coils Insulation DPC (Rectangular)	Per Kg	80.27
6		Labour Charges for preparation and fitting of finished new Aluminium Coil by providing new inter-layer insulation		
	(A)	11 KV 6.6/6 KV Coils		
	i)	Insulation DPC (Round)	Per Kg	74.26
	ii)	Insulation SE (Round)	Per Kg	75.07
	(B)	400 Volts Coils (with ducting)		

Sl. No.		Description of Items	Unit	Rate (Rs.) without GST
	i)	Insulation DPC (Round)	Per Kg	74.26
	ii)	Insulation DPC (Rectangular)	Per Kg	74.26
7	(A)	Labour Charges for rewinding with replacement of inter-layer insulation of old Aluminium Wire : 11/6.6 KV Coils (DPC/TPC) (Inter layer insulation material is to be used as per recommendation of manufacturer of Insulating material)	Per Kg	92.13
	(B)	Labour Charges with re-insulation of existing 400 Volts KV Aluminium Coils by providing new inter-layer insulation with ducting (Inter layer insulation material is to be used as per recommendation of manufacturer of Insulating material)	Per Kg	60.81
8		Re-Assembly and Boxing up of Core and Coil after through cleaning, drying and reconnection of Coils including testing charges (Double Voltage Double Frequency test included)		
	a)	10/16/25 KVA, 11/6.6/6/0.433 KV	Each	2860.36
	b)	50 /63 KVA, 11/6.6/6/0.433 KV	Each	3588.41
	c)	100/160 KVA, 11/6.6/6/0.433 KV	Each	4362.90
	d)	250 KVA, 11/6.6/6/0.433 KV	Each	5584.11
	e)	315 KVA, 11/6.6/6/0.433 KV	Each	5584.11
	f)	500/630 KVA, 11/6.6/6/0.433 KV	Each	7344.88
	g)	50 KVA, 33/0.433 KV	Each	3588.41
	h)	100 KVA, 33/0.433 KV	Each	4344.93
	i)	250 KVA, 33/0.433 KV	Each	3722.84
9		External Painting of Transformers		
	a)	10/16/25 KVA, 11/6.6/6/0.433 KV	Each	571.62
	b)	50/63 KVA, 11/6.6/6/0.433 KV	Each	872.46
	c)	100/160 KVA, 11/6.6/6/0.433 KV	Each	1249.28
	d)	250 KVA, 11/6.6/6/0.433 KV	Each	1746.87
	e)	315 KVA, 11/6.6/6/0.433 KV	Each	1872.21
	f)	500 /630 KVA, 11/6.6/6/0.433 KV	Each	2522.52
	g)	50 KVA, 33/0.433 KV	Each	806.04
	h)	100 KVA, 33/0.433 KV	Each	1249.28
	i)	250 KVA, 33/0.433 KV	Each	1809.80
10		Transformer Tank repairing charges for Electrical Welding	Per running	59.00
11		Gas Cutting of lit of sealed type transformer	Per running	198.00
12		Filtration of Insulating Oil at suitable temperature in steam line atype filter machine		
	i)	New/reclaimed Oil (Process loss 2%)	Per Ltr.	6.00

Annexure-C : Final Price List i.r.o. Labour & Supervisory Items for Repairing of Damaged/Defective Wound Core Type DTR (NIT No.: P- 35/ 2017-18/ DTR/ RC/ PC-III, opened on 09/03/2018)

Sl. No.		Description of Items	Unit	Rate (Rs.) without GST
1		Joint preliminary/final survey and preparation of report together with estimate of repair work involved (to be submitted in quadruplicate)		
	a)	10 KVA/16 KVA/25 KVA/, 11/6.6/6/0.433 KV	Each	1109.90
	b)	50 KVA/63 KVA, 11/6.6/6/0.433 KV	Each	1156.10
2		Re-assembly of Transformer found condemned after inspection		
	a)	10 KVA/16 KVA/25 KVA, 11/6.6/6/0.433 KV	Each	383.60
	b)	50 KVA/63 KVA, 11/6.6/6/0.433 KV	Each	490.40

Sl. No.		Description of Items	Unit	Rate (Rs.) without GST
3		Labour Charges for preparation and fittings of new Copper Coil in replacement of damaged ones by providing inter-layer insulation (Inter layer insulation material is to be used as per recommendation of manufacturer of Insulating material)		
	(A)	11/6.6/6 KV Coils		
	i)	HV Coils Insulation SE	Per Kg	89.90
	(B)	400 Volts Coils		
	i)	LV Coil Insulation DPC (Round)	Per Kg	69.30
	ii)	LV Coil Insulation DPC (Rectangular)	Per Kg	69.30
4		Labour Charges for rewinding with re-insulation with inter-layer insulation of old LV (400/415/433 Volts) Copper Coil with ducting (Inter layer insulation material is to be used as per recommendation of manufacturer of Insulating material)		
	a)	LV Coils Insulation DPC (Round)	Per Kg	80.27
	b)	LV Coils Insulation DPC (Rectangular)	Per Kg	80.27
5		Labour Charges for preparation and fitting of finished new Aluminium Coil by providing new inter-layer insulation		
	(A)	11 KV 6.6/6 KV Coils		
	i)	Insulation SE (Round)	Per Kg	92.40
	(B)	400 Volts Coils (with ducting)		
	i)	Insulation DPC (Round)	Per Kg	92.40
	ii)	Insulation DPC (Rectangular)	Per Kg	92.40
6		Labour Charges for rewinding with re-insulation of existing 400 Volts KV Aluminium Coils by providing new inter-layer insulation with ducting (Inter layer insulation material is to be used as per recommendation of manufacturer of Insulating material)	Per Kg	62.70
7		Re-Assembly and Boxing up of Core and Coil after through cleaning, drying and reconnection of Coils including testing charges (Double Voltage Double Frequency test included)		
	a)	10/16/25 KVA, 11/6.6/6/0.433 KV	Each	3798.90
	b)	50/63 KVA, 11/6.6/6/0.433 KV	Each	4765.90
8		External Painting Transformers		
	a)	10/16/25 KVA, 11/6.6/6/0.433 KV	Each	571.62
	b)	50/63 KVA, 11/6.6/6/0.433 KV	Each	872.46
9		Transformer Tank repairing charges for Electrical Welding	Per running	59.00
10		Gas Cutting of lit of sealed type transformer	Per running	198.00
11		Filtration of Insulating Oil at suitable temperature in steam line type filter machine		
	i)	New/reclaimed Oil (Process loss 2%)	Per Ltr.	6.00